

UTTAM SUGAR MILLS LTD.,

Unit- Libberheri

Building Detail

| SL. No. | Factory Building | Particular | Size(in Meter) | Type of Construction |
|---------|------------------|----------------------------|-----------------------|----------------------------------------|
| A | Main Building | Mill House | 91x25x20 Mtr. HT. | Steel Structure with RCC & Bricks Work |
| | | Boiler | 61x26x27 Mtr. HT. | Steel Structure with RCC & Bricks Work |
| | | Power House | 70x25x20 Mtr. HT. | Steel Structure with RCC & Bricks Work |
| | | Evaporation House | 42x25x27 Mtr. HT. | Steel Structure with RCC & Bricks Work |
| | | Clarification House | 36x30x27 Mtr. HT. | Steel Structure with RCC & Bricks Work |
| | | Raw Pan House | 72x26x30 Mtr. HT. | Steel Structure with RCC & Bricks Work |
| | | Sugar House | 30x26x30Mtr. HT. | Steel Structure with RCC & Bricks Work |
| | | Refinery | 50x25x 25Mtr. HT. | Steel Structure with RCC & Bricks Work |
| | | Mill House D.C. Panel Room | 30x6x3 Mtr. HT. | Brick Wall & RCC |
| | | Fibrizor Panel Room | 8x5.7x4 Mtrs. | Brick Wall & RCC |
| | | Invert Syrup Store | 16.5x3.6x3.6 Mtr. HT. | Bricks Wall with RCC |
| | | Chemist Office | 7.5x3.6x3.6 Mtr. HT. | Bricks Wall with RCC |
| | | Engineering Office | 3.5x3.6x3.6 Mtr. HT. | Bricks Wall with RCC |
| | | HOD Engineering Office | 12x3.6x3 Mtr. HT. | Bricks Wall with RCC |
| | | Instrument Office | 19x3.8x4 Mtr. HT | Bricks Wall with RCC |
| | | Boiler Control / VFD Room | 19x3.8x4 Mtr. HT | Bricks Wall with RCC |
| | | Boiling House Panel Room | 30x3.6x3 Mtr. HT. | Bricks Wall with RCC |
| | | Branded Unit Scrap | 15x4.5x3 Mtr.. HT | Steel Structure with RCC & Bricks Work |
| | | Branded Dmerera Room | 27x4.5x3 Mtr. HT. | Steel Structure with RCC & Bricks Work |
| | | Store | 14.6x24x6 mtrs. | Steel Structure with RCC |
| | | Bagasse Yard | 47x51x16 Mtr. HT. | Steel Structure with RCC |
| | | Kisan Shed | 27x4.5x3 Mtr. HT. | Brick Wall with G.I. Sheet Roof. |

| SL. No. | Factory Building | Particular | Size(in Meter) | Type of Construction |
|---------|------------------|-----------------------------------|---------------------|----------------------------------------|
| | | Token Room No. 1 | 5x2.6x2.5 Mtr. HT. | Brick Wall with RCC Roof Slab |
| | | Token Room No. 1 | 5x2.6x2.5 Mtr. HT. | Brick Wall with G.I. Sheet Roof. |
| | | Cane Enquire Office | 5x4x2.5 Mtr. HT. | Brick Wall with RCC Roof Slab |
| | | Cane Weighing Bridge Room Trolley | 4x3.5x3 Mtr. HT. | Brick Wall with RCC Roof Slab |
| | | Cane Weighing Bridge Room Center | 4x3.5x3 Mtr. HT. | Brick Wall with RCC Roof Slab |
| | | Cane Weighing Bridge Room Cart | 4x3.5x3 Mtr. HT. | Brick Wall with RCC Roof Slab |
| | | Cane Supervisor Office | 4x3.5x3 Mtr. HT. | Brick Wall with RCC Roof Slab |
| | | Lime Store | 11x5.8x4 Mtr. HT. | Brick Wall with RCC Roof Slab |
| | | Cement Store | 11x5.8x4 Mtr. HT. | Brick Wall with RCC Roof Slab |
| | | | | |
| B | Sugar Godown | Sugar Godown No.-1 | 90x45x17Mtr. HT. | Steel Structure with RCC & Bricks Work |
| | | Sugar Godown No.-2 | 100x50x17Mtr. HT. | Steel Structure with RCC & Bricks Work |
| | | Sugar Godown No.-3 | 100x50x17Mtr. HT. | Steel Structure with RCC & Bricks Work |
| | | Sugar Godown No.-4 | 100x13x11Mtr. HT. | Steel Structure with RCC & Bricks Work |
| | | | | |
| C | Office Block | Technical Block | 17x20x4 Mtr. HT. | Bricks Wall with RCC |
| | | Lab. | 12.5x8.4x3 Mtr. HT | Bricks Wall with RCC |
| | | Micro Lab. | 8.4x7.8x3Mtr. HT. | Bricks Wall with RCC |
| | | Toilet Tech. Block | 7x2.5x3 MTR. HT | Bricks Wall with RCC |
| | | Ttime Office | 9.5x5x3 Mtr. HT. | Bricks Wall with RCC |
| | | Toilet Time Office | 4x2x2 Mtr. HT. | Bricks Wall with RCC |
| | | Account Office | 24x3.6x3.1 Mtr. HT. | Bricks Wall with RCC |
| | | Dispensary | 3x3.6x3 Mtr. HT. | Bricks Wall with RCC |
| | | Cane Office | 46x6x3 Mtr. HT. | Bricks Wall with Cement Sheet |
| | | Toilet Cane Office | 4x4x3 Mtr. HT. | Bricks Wall with Cement Sheet |
| | | Toilet Branded Unit | 6x3x3 Mtr. HT. | Bricks Wall with RCC |

| SL. No. | Factory Building | Particular | Size(in Meter) | Type of Construction |
|---------|-----------------------|--------------------------|---------------------|-------------------------------------------|
| | | Sales Office | 9x4.7x3 Mtr. HT. | Bricks Wall with Cement Sheet |
| | | Secuirty Office | 3.8x2.5x3 Mtr. HT. | Bricks Wall with Cement Sheet |
| | | Toilet Kisan | 3x2.5x3 Mtr. HT. | Bricks Wall with Cement Sheet |
| | | Dispensary | 3x3.6x3 Mtr. HT. | Bricks Wall with RCC |
| | | Canteen | 18x6.6x3.2 Mtr. HT. | Bricks Wall with Cement Sheet |
| | | | | |
| D | Guest House | Guest House (VIP) | 22x10x3 Mtr. HT. | Bricks Wall with RCC & G.I. sheet |
| | | Guest House Officer | 26x10x3 Mtr. HT. | Bricks Wall with RCC & G.I. sheet |
| | | Officer Colony | 100x18x3Mtrs. | Bricks Wall with RCC |
| | | Guest House No.-2 | 90x6x3 Mtr. HT. | Bricks Wall with Cement sheet |
| | | Cow Sheed | 60x20x3 Mtr. HT. | Bricks Wall with Cement sheet |
| | | Labour Colony (35 Room) | 120x4x3Mtr. HT. | Bricks Wall with GI Sheet |
| | | | | |
| E | ETP Building | Panel Room | 12x4x3 Mtr. HT. | Bricks Wall with RCC |
| | | Lagoon | 180x25 | Brick Work |
| | | | | |
| F | Sub. Station Building | Switch Yard | 29x22 Mtr. HT. | Steel Structure Bracading with Brick Work |
| | | HT. Cable Trenches | 100x1.2x1.1 M | Brick Work |