



# deepak Poly-Plast Pvt. Ltd.

REGD. OFFICE: 802 , 8<sup>TH</sup> FLOOR,SHIVALIK SHILP  
ISCON CROSS ROAD, S. G. HIGHWAY,  
AHMEDABAD-380054 (GUJARAT) INDIA.  
E-mail: exports@deepakpolyplast.com  
Website: www.deepakpolyplast.com  
PH: +91 79 29700342 , 29700431 , 9227153090



**A N I S O 9 0 0 1 : 2 0 0 8 C O M P A N Y**

INQ. NO: DPPL/PCI/01/21-22/01336

DATE: 19 / 02 / 2022

REF. NO: DPPL/PCI/03/21-22/01336

DATE: 19 / 02 / 2022

TO,  
**M/S POLYPALS GLOBAL PVT. LTD.**  
H. NO. 34, RK ENCLAVE,  
HARIDWAR, UTTARAKHAND,

PHONE: 9427801952  
E-MAIL : [bhagwan75negi@gmail.com](mailto:bhagwan75negi@gmail.com)  
REF: TELE ENQUIRY  
Dtd.: 19 / 02 / 2022

**KIND ATTN: MR. BHAGWAN JI**

**SUB: QUOTATION FOR PLASTICS TESTING M/C's AS PER REQUIREMENT.**

**QUOTATION HS CODE : 9024**

SR. NO	DESCRIPTION	RATE (Rs.)
01.	HOT AIR CIRCULATING OVEN UNIT INNER CHAMBER SIZE: 18 X 18 X 18 inch FOR REVERSION TEST APPLICATION	48,000 = 00

>> WITH DIGITAL PID TEMP.CONTROLLER PANEL FITTED.  
WITH INBUILT DIGITAL TIMER SYSTEM ALONG WITH BUZZER FACILITY.  
WITH INBUILT AND AIR CIRCULATING FAN SYSTEM FITTED.  
>> TEMP.CONTROLLER: MAKE: PPI-ZENEX / TOHO / OMRON - 48 X 48.  
WITH AUTOTUNE FACILITY.  
>> DIGITAL DISPLAY RANGE OF TEMP.CONT.: UPTO 400.0 DEG.C.  
LEAST COUNT: 0.1 DEG.C.  
WORKING ACCURACY: +/- 1 DEG.C.  
WORKING TEMPERATURE RANGE: FROM ROOM TEMP. TO 180 DEG.C.  
>> INNER CHAMBER SIZE: 18 x 18 x 18 inch (450 x 450 x 450 mm)  
INSIDE COMPLETE SS (SS-304) CHAMBER WITH BUFFING, OUTSIDE MS  
SHEET FABRICATED BODY.  
>> COMPLETE INSULATED CHAMBER WITH 2.5 inch THICK GLASSWOOL  
INSULATION (DOUBLE WALLED CHAMBER)  
>> WITH 02 NOS. OF HEAVY SS PIPING MADE TRAY FITTED INSIDE.  
>> POWER REQUIREMENT: 220/230V AC - SINGLE PHASE 50/60 Hz-15 AMP

PAGE:-01 OF 09

CONT.....

WORKS: PLOT NO: 198/1-2, Nr.DEEP KIRAN FOOD PRODUCTS, G.I.D.C. DANTALI, AT DANTALI  
VIA: LAPKAMAN VILLAGE, GOTA - VADSAR ROAD, TAL: KALOL, DIST: GANDHINAGAR  
(GUJARAT) INDIA TEL: +91-9228002183



02. DIGITAL WEIGHING BALANCE 21,500 = 00  
300 gms CAPACITY (GSM WEIGHING SCALE)

**READABILITY: 0.001 GMS (1 mg)**

**PAN SIZE: 80 mm**

**RESPONSE TIME: 3-5 SEC.**

**CALIBRATION: AUTOMATIC - EXTERNAL**

**OPERATING TEMP.: 10 TO 40 DEG.C.**

**DIMENSION: 316 X 210 X 308 MM**

**6 KG WEIGHT.**



**HOT AIR OVEN**



**WEIGHING BALANCE**



---

03. TENSILE TESTING MACHINE. 2, 79,000 = 00  
MODEL: DUTT - 101  
MACHINE STRUCTURE CAPACITY: UPTO 750 KGF

---

- >> SINGLE SCREW FLOOR MOUNTING MACHINE.  
WITH COMPLETE PU PAINT STRUCTURE.
- >> EQUIPPED WITH MAXIMUM 250 KGF CAPACITY ELECTRONIC LOADCELL.  
MODEL: 20210, "S" SHAPE, MAKE: ADI ARTECH.  
EQUIPPED WITH MECHANICAL WISE TYPE GRIP SET (SMOOTH NURLING TYPE)  
FOR HDPE / LDPE SPECIMEN TESTING APPLICATION.
- >> WITH LCD BASED DISPLAY PANEL TO GET MAX. LOAD, ELONGATION & ALL  
CALCULATED TEST RESULTS.
- >> WITH HEAVY DUTY MS CASTING STRUCTURE FOR VIBRATION LESS TESTING.
- >> WITH COMPUTER INTERFACING SOFTWARE SYSTEM TO GET ONLINE  
GRAPH & CALCULATED RESULTS TABLE.
- >> WITH INTERFACING CABLE & SOFTWARE CD.
- >> WITH AC FREQUENCY "DELTA MAKE" VARIABLE SPEED DRIVE SYSTEM.  
SPEED SELECTION: 50 mm/min TO 500 mm/min.
- >> WITH 01 SET OF MECHANICAL WISE TYPE GRIP SET, SUITABLE FOR HDPE/LDPE  
EXTRUDED HARD SAMPLES.
- >> WITH FOUNDATION LEGS & BASE MOUNTING.
- >> MACHINE IS HAVING AUTO REVERSE FACILITY .AFTER COMPLETION OF  
TEST, MACHINE WILL AUTO REVERSE TO THE STARTING POSITION  
AUTOMATICALLY.
- >> WITH AUTO REPORT GENERATION IN WINDOWS EXCEL SYSTEM, WHERE  
BUYER'S COMPANY NAME, COMPANY LOGO FEEDING FACILITY IS AVAILABLE.
- >> GENERATED REPORT SAVING IN YOUR PC SYSTEM AND CAN BE CONVERTED IN  
pdf. AND ALSO CAN BE SEND FROM ONE PLACE TO ANOTHER PLACE AS  
E-MAIL ATTACHMENT.
- >> WITH EMERGENCY STOP FACILITY ON PANEL (FOR SAFETY REASONS)
- >> PANEL EQUIPPED WITH MAIN MCB SWITCH FOR BETTER SAFETY DURING  
OPERATION.
- >> WITH ONE YEAR FACTORY CALIBRATION CERTIFICATE, ALONG WITH NABL  
TRACEBELITY SUPPORT. WITH COMPLETE OPERATING MANUAL (WITH  
PICTURES), WIRING DIAGRAM, AND MACHINE OPERATION AND FLOW  
DIAGRAMS.



# deepak Poly-Plast Pvt. Ltd.

REGD. OFFICE: 802 , 8<sup>TH</sup> FLOOR,SHIVALIK SHILP  
ISCON CROSS ROAD, S. G. HIGHWAY,  
AHMEDABAD-380054 (GUJARAT) INDIA.  
E-mail: exports@deepakpolyplast.com  
Website: www.deepakpolyplast.com  
PH: +91 79 29700342 , 29700431 , 9227153090



**A N I S O 9 0 0 1 : 2 0 0 8 C O M P A N Y**

---

## SOFTWARE FEATURES:

- ⇒ UNIT CONVERSION FACILITY.
- ⇒ ONLINE GRAPH PLOTTING.
- ⇒ RESULT COMPARISON UPTO 5 SAMPLES.
- ⇒ GRAPH LINE COLOUR SELECTION.
- ⇒ WINDOWS BASED USER FRIENDLY SOFTWARE.
- ⇒ DIRECT REPORT GENERATION IN EXCEL.

---

**NOTE:** COMPUTER WITH PRINTER IS NECESSARY AT BUYER'S END FOR THE ABOVE TENSILE TESTING M/C.  
MODEL: DUTT-101 – SINGLE SCREW- FLOOR MODEL.

## **CONFIGURATION REQUIRED:**

INTEL ® PENTIUM-IV, CPU-2.40 GB, 128 MB RAM, 40 GB HDD, 52x CD –DRIVE, SERIAL PORT (COMPORT) RS. 232,  
WITH MICROSOFT WINDOWS XP-PROFESSIONAL “OR” MICROSOFT WINDOWS 98 (SECOND EDITION), WITH  
MICROSOFT OFFICE - XP FULL INSTALLATION.

**ALSO COMPETIBLE WITH WINDOWS – 7, 8.1 & 10 VERSIONS.**

---

## **04. TENSILE TESTING ACCESSORIES.**

---

>> TEMPLATE FOR SPECIMEN PUNCHING, FOR TENSILE TEST.

RECTANGULAR SIZE: 150 x 25 mm ===== > 01 UNIT =====➔ 4,500 = 00

---



05. IZOD - CHARPY IMPACT TESTING MACHINE 1, 49,000 = 00  
WITH DIFFERENT JOULE SCALE -  
DIGITAL VERSION DIGITAL DISPLAY OF READINGS  
MAXIMUM UPTO 25 JOULES

SUITABLE AS PER ASTM D 256 & ISO 180 / ASTM D 6110 & ISO 179

- >> STANDARD SPECIFICATIONS ARE AS PER ASTM-D-256.  
>> MEASUREMENT RANGE: UP TO 25 JOULE ON DIGITAL DISPLAY UNIT.  
>> ACCURACY: 0.01J IN COMPLETE RANGE. (ON FULL SCALE READING).  
>> DISPLAY: DIGITAL DISPLAY OF READINGS.  
>> CANTILEVER HOLDING TYPE SPECIMEN HOLDING FIXTURE FOR IZOD TEST.  
>> SUPPORTED BEAM TYPE SPECIMEN HOLDING FIXTURE FOR CHARPY TEST.  
>> POWER REQUIREMENT: 220-230V AC SINGLE PHASE - 15 AMP. @ 50-60 Hz



## **OTHER FEATURES:**

- ⇒ **DROPPING HEIGHT : FIXED AT 0.61 m.**
- ⇒ **PENDULAM CAPACITY: UPTO 25 JOULES (WITH THREE SETS OF LOADS FOR 7.5 JOULES, 15 JOULES & 25 JOULES)**
- ⇒ **IMPACT VELOCITY : 3.46 m/s**
- ⇒ **WITH AUTO CALIBRATION FACILITY FOR BEARING WIND EDGE AND FRICTION**
- ⇒ **ENERGY DISPLAY IN JOULES UNIT ONLY**
- ⇒ **WITH DIGITAL LCD BASED DISPLAY UNIT**



**IZOD – CHARPY IMPACT TESTING MACHINE**





06. MANUALLY OPERATED NOTCH CUTTER 39,000 = 00

**SUITABLE AS PER ASTM D 256 & ISO 179**

>> THE LINEAR NOTCHING MACHINE IS DESIGNED TO PREPARE RAPID &  
ACCURATELY NOTCHES SPECIMEN FOR IMPACT RESILIENCE DETERMINATIONS  
ACCORDING TO IZOD, CHARPY IMPACT METHODS.  
>> MANUAL OPERATION BASED ON HAND WHEEL.

MANUALLY OPERATED NOTCH CUTTER



## ➔ COST STRUCTURE

**BEST OFFERED BASIC VALUE : Rs. 5, 41, 000 = 00**

### **FINAL OFFER**

**PACKING CHARGES : Rs. 8, 100 = 00**

**TRANSPORTATION CHARGES : RS. ON TO PAY BASIS**

**SUB TOTAL : Rs. 5, 49, 100 = 00**

**18% IGST EXTRA : Rs. 98, 838 = 00**

**TOTAL VALUE OFFERED : Rs. 6, 47, 938 = 00**  
**(EX-WORKS, AHMEDABAD-INDIA) \*\*\*\*\***



## SALES TERMS & CONDITIONS

1. PRICE BASED ON : EX-WORKS, AHMEDABAD – INDIA
2. PACKING CHARGES : EXTRA AT ACTUAL, AS SHOWN ABOVE.
3. TAX : 18% IGST EXTRA AS APPLICABLE
4. TRANSPORTATION : BY ANY REPUTED ROAD TRANSPORTER-BY ROAD
5. FREIGHT : EXTRA AS APPLICABLE END, ON TO-PAY BASIS.
6. INSURANCE : FROM CUSTOMER END, AGAINST DESPATCH ADVICE.
7. ERRECTION AT SITE : **Rs. 12,500/= + IGST 18%** EXTRA FOR INSTALLATION & TRAINING AT YOUR SITE. (INCLUDES TO & FRO + ACCOMODATION + DAILY EXP.) (IF REQUIRED)
8. TERMS OF PAYMENTS : 30 % ADVANCE ALONG WITH P.O. BALANCE 70% AT THE TIME OF INSPECTION, AT OUR END, BEFORE DESPATCH
9. DELIVERY PERIOD : **WITHIN 06 WEEKS FROM THE DATE OF PURCHASE ORDER ALONG WITH ADVANCE PAYMENT.**
10. VALIDITY OF OFFER : -----30 DAYS-----
11. GST & ARN NO. : **24AAACD6653R1Z7**      AA241116011597G
12. CALIBRATION CERTIFICATES: **WITH NABL LAB TRACEBELITY** : **“DPPL” WILL PROVIDE FACTORY ISSUES CALIBRATION CERTIFICATES WITH NABL LAB TRACEBELITY.**
13. INSPECTION : PRE-DESPATCH INSPECTION BY **M/S POLYPALS GLOBAL PVT. LTD.** RESENTITIVE AT OUR WORKS
14. WARRANTY : ONE YEAR SERVICE WARRANTY AGAINST ANY MANUFACTURING DEFECTS, ON TO & FRO CHARGABLE BASIS + ACCOMODATION.
15. CANCELLATION OF ORDER : ONCE FOR THE ORDER FOR THE MACHINE PLACED, ORDER WILL NOT BE CANCELLED FOR ANY REASONS WHATSOEVER, IN CASE OF CANCELLATION, THE ENTIRE AMOUNT OF THE ADVANCE WILL BE FORFEITED

**NOTE: NO GUARANTEE FOR ELECTRONIC LOADCELL UNITS, ELECTRONIC SENSORS / THERMOCOUPLES, SOLID STATE RELAY (SSR) CONTACTORS, GLASS ITEMS, ELECTRONIC PRESSURE TRANSDUCERS, IMMERSION HEATERS, CHILLER GAS, GLASSWARES & RUBBER PARTS FITTED IN MACHINES / SUPPLIED WITH MACHINES.**

**NOTE: NO GAURANTEE / WARRANTEE FOR ELECTROPLATTING / POLISH WORK / BUFFING WORK.**





# deepak Poly-Plast Pvt. Ltd.

REGD. OFFICE: 802 , 8<sup>TH</sup> FLOOR,SHIVALIK SHILP  
ISCON CROSS ROAD, S. G. HIGHWAY,  
AHMEDABAD-380054 (GUJARAT) INDIA.  
E-mail: exports@deepakpolyplast.com  
Website: www.deepakpolyplast.com  
PH: +91 79 29700342 , 29700431 , 9227153090



**A N I S O 9 0 0 1 : 2 0 0 8 C O M P A N Y**

---

I/WE AGREE TO SUPPLY TESTING M/Cs & ACCESSORIES TO **M/S POLYPALS GLOBAL PVT. LTD.**, WITH THE ARTICLES SPECIFIED ABOVE UPON THE TERMS & CONDITIONS AND CONTRACT GIVEN ABOVE. THE ACCEPTANCE OF THIS QUOTATION BY **M/S POLYPALS GLOBAL PVT. LTD.** SHALL CONSTITUTE A BINDING CONTRACT BETWEEN ME/US AND **M/S POLYPALS GLOBAL PVT. LTD.**

**THANKING YOU,**

**YOURS TRULY,  
FOR, DEEPAK POLY PLAST PVT LTD.**

**RAJESH ASRANI  
DIRECTOR – Mktg (CELL: +91 98240 76791)**

---

**PAGE: 09 OF 09**

**WORKS: PLOT NO: 198/1-2, Nr.DEEP KIRAN FOOD PRODUCTS, G.I.D.C. DANTALI, AT DANTALI  
VIA: LAPKAMAN VILLAGE, GOTA - VADSAR ROAD, TAL: KALOL, DIST: GANDHINAGAR  
(GUJARAT) I N D I A TEL: +91-9228002183**