

S.N ENGINEERING WORKS

Deals in : Manufacturer of Tank & Vessels, Heavy Structure Steel Fabrication, Boiler Erection & services ,ETP STP & WTP
Manufacturer, Turnkey Projects of Honey, Pharmacy, Food, Power and Foundry Plant, Piping Projects, Panel Designing, Industrial
Wiring ETC.

Mob: 8958037955,9997040733

GST NO: 05EYPS7255HIZH

Email: snengineering1985@gmail.com

QUOTATION

TO,

Date-25.11.2022

PARRISH PHARMACEUTICALS PVT LTD
Plot no- 50,Sector 8A IIE Sidcul Haridwar

Kind Attn. RAVIKANT JI

Sub.: Quotation for Reverse Osmosis water plant R-O based capacity 1000 with DM water tank .

Dear Sir,

This refers to our discussion with you at your residence regarding your requirement of above subject matter. We appreciate your interest in our range of products. We are Indicating below Price & Terms Condition for your kind consideration.

Price: Prices As mentioned blow.

1.Supply of Water Treatment plant R.O. based Cap. 1000 LPH -----	Rs.3,95,000.00
2 DM WATER SS JACKETED TANK 2000 LTR , -----	RS 530000.00
3 RO Pipe Line SS fitted line -----	RS 165000.00
4 Mixed Wad -----	Rs 215000.00
5. SS SOFTNER -----	Rs 150000.00
6. SS loop line works -----	R s 465000.00
7. Loop pump 7.5 hp with trolley ---	RS 85000.00

TOTAL- -----	Rs 2005000.00
GST 18% -----	Rs 360900.00
Net Total -----	Rs 2365900.00

Amount in word: Twenty three lakh sixty five thousand nine hundred rupees only

Payment Terms

50% as advance.

50% before dispatches

TERMS & CONDITIONS

GST

18% Extra

Freight

To pay at actual

Validity

30 days from the date of the offer.

Delivery

within 10-20 days.

Thanking you and awaiting your reply at the earliest.

Yours Faithfully,

For S N ENGINEERING WORKS

(Marketing Division)

SCOPE OF SUPPLY (1000 LPH R.O Plant

→ RAW WATER TANK (SSTANK)

QUANTITY	:	01 No
CAPACITY	:	1200 Ltr.
MATERIALS	:	HDPE

→ RAW WATER PUMP

QUANTITY	:	1.0 Nos.
TYPE	:	HORIZONTAL CENTRIFUGAL TYPE
M.O.C	:	C.I
CAPACITY	:	1.5. HP/2900 rpm
MAKE	:	Kirloskar/Equiv.

→ MULTI GRADE FILTER

QUANTITY	:	01 No
VESSEL SIZE	:	13" dia X 54" ht
VESSEL MATERIAL	:	SS grade
OPERATING PRESSURE	:	05-3.0 kg/cm ²
MEDIA TYPE	:	GRADED SILEX & SAND

→ ACTIVATED CARBON FILTER

QUANTITY	:	01 No
VESSEL SIZE	:	. 13" dia X 54" ht
VESSEL MATERIALS	:	SS grade
OPERATING PRESSURE	:	0.5-3.0 kg/cm ²
MEDIA TYPE	:	ACTIVATED CARBON

→ SOFTER FILTER

QUANTITY	:	01 No
VESSEL SIZE	:	. 13" dia X 54" ht
VESSEL MATERIALS	:	SS grade
OPERATING PRESSURE	:	0.5-3.0 kg/cm ²
MEDIA TYPE	:	ACTIVATED

→ OPERATION SYSTEM

QUANTITY	:	02 Nos
TYPE	:	Semi Automatic
FLOW MOUNTING UNIT	:	Multi Port valve

→ CARTRIDGE FILTER

QUANTITY	:	01 No.
----------	---	--------

FILTRATION RATING	:	5 MICRON
FILTER MATERIAL	:	PP
FILTER SIZE	:	20"
HOUSING SIZE	:	20" (Big-Blue)

→ **R.O FEED PUMP**

QUANTITY	:	01 No.
MATERIAL	:	SS
OPERATING PRESSURE	:	0-3.5 kg/cm2
TYPE	:	Centrifugal TYPE PUMP
MAKE	:	Leo/EQUV.
TYPE OF DRIVE	:	Single-phase/2900 rpm

→ **R-O UNIT**

MEMBRANES	:	04No
TYPE	:	4040
SIZE	:	4" dia X 40" Length
MATERIAL	:	Composite Polyamide
MAKE	:	LG/Equiv.
VESSEL	:	1.0 Nos. (2E)
MAKE	:	MATRIX/ROH
RATING	:	250 PSI
MATERIAL	:	FRP

→ **CONTROL INSTRUMENTS**

*Permeate Flow meter (Panel mounted)
Reject (concentrate)flow-meter(panel mounted)
Pressure gauges are fitted on wet panel & Pre-filtration unit
(MGF & ACF) and its accessories.
Low & High Pressure Switches.*

→ **Conductivity/TDS meter with sensor 01 No.**

→ **CONTROL PANEL WITH PLC SYSTEM 01NO.**

Panel Box	SS Skid Mounted Electrical Components make	L&T/Standard
-----------	--	--------------

→ **FLUSHING SYSTEM 01 No.**

Flushing tank MOC, Capacity	HDPE, 100Ltr.
Cleaning / flushing pump	centrifugal mono-bloc type
Make, power required RPM	Leo/Equiv. 1.0 HP/2900 rpm
	Flushing Filter 20"PP Housing, 01 x 5.0μ - 20" cartridge

→ **WET PANEL 01NO.**

→ **Skid (Pre-filtration + R.O) 02 Nos.**

→ **Piping & Fittings (UPVC) 01Lots**
(Astral make)

MIXED WAD WITH 2HP COMPRESSOR

TERMINATION POINTS

1. Raw water Facility up to R.O Plant
2. Power facility up to the plant.
3. Provision of drain.

CLIENT'S RESPONSIBILITY

- 1 Power Supply
- 2 Service Water
- 3 Labour
- 4 Shade or plant room will be arranged by you.
- 5 FRP Tank for RO storage purpose 1000 ltr

Sub: QUOTATION OF SS -316 JACKETED TANK FOR DM PLANT -2000 LTR**❖ All contact and non contact part made out of SS- 316**

1	MANUFACTURING VESSEL	
1	Content	Water
2	Gross Capacity	2000 LTRS.
3	Working Capacity	2100 LTRS.
4	Type of Vessel	Vertical , Cylindrical,
5	Top Ends	Dish type Fitted with manhole
6	Bottom Ends	Dish Type
7	Vessel Supports Pedestal	4Nos. With Base Plate
A	DIMENSIONS OF MFG. VESSEL	
1	SS-316 Inner cell .	I/D 1300 mm. x 4mm. Thk(H-1600))
	SS-304 Outer cell	I/D 1400 mm. x 4mm. Thk(H-1500))
	SS-304 Insulation cell	I/D 1500 mm. x 2mm. Thk(H-1600))
2	SS-316 Top	I/D 1300 mm. x 4mm. Thk(H-2200)
3	SS-316 Bottom Conical Dish	I/D 1300mm. x 4mm. Thk.(H-150)
4	SS-316 Bottom conical Dish	I/D 1400mm. x 4mm. Thk.(H-150)
	SS-316 Insulation bottom conical dish	I/D 1500mm. x 2mm. Thk.(H-150)

COLNEL'S ENCLAVE ROORKEE NEAR BHAWANI SHANKAR ASHRAM DIST -HARIDWAR (UK)-
247667

Mob: 8958037955,7310803703

Email: snengineering1985@gmail.com

B		NOZZLE SCHEDULE FOR VESSEL	QTY.	SIZE	Material	REMARKS
	N2	N 2 Outlet connection	1No.	50mm	SS-316	Flanged
	N3	N 3 Air Vent	1No.	25mm	SS-316	
	N4	N 4 Steam inlet	1No.	25mm	SS-316	
	N5	N 5 Main Hole	1No.	450mm	SS-316	
	N6	N 6 Steam Outlet	1No.	25mm	SS-316	
5		Electrical Heater 9kw – 3 heater fitted				
6		SS Pannel for the operation temp controller , off / on switch				
2		Mirror FINISH Internal and outside.				
3		DOCUMENTATION SUBMITTED				
	1	SS Material Test Certificate & Test Certificate Bought outs Items,				
	2	DQ,				

S.NO.	Part no.	Description Goods	Qty.	Unit.	List price	Amount
1		SS 316 MANUFACTURING TANK WITH JACKET 2000 LTR WEIGHT(APPROX – 1100 KG)	1	Nos.	530000.0	530000

In case of queries about the offer, please feel free to contact us

Terms & Condition:

(GST extra)

②.Packing & Forwarding: Extra

②.Freight: Extra on to pay basis.

②. Installation charges: Installation would be in client scope.

②.Tax: applicable 18%GST will apply at time of final billing.

②. Warranty period: Warranty is void in case of accident / mishandling / service by unauthorized personnel.

②. Delivery period: 2-3 week after PO with advance.

②. Payment: 50% advance with order confirmation, 40%payment against delivery 10% after installation.

. Our equipments are manufactured as per the details provided in our quotation/catalogue, but due to the company's policy of continuous development and improvement, we reserve the right to change or modify the design or construction without notice.

COLNEL'S ENCLAVE ROORKEE NEAR BHAWANI SHANKAR ASHRAM DIST –HARIDWAR (UK)-247667

Mob: 8958037955,7310803703

Email: snengineering1985@gmail.com