

## BST Textile Mills Pvt. Ltd.

## GSTIN NO. - 05AACCB7130PZL Service Order


To
AALA TECHNOCRAT
G-7, ABUL FAZAL ENCLAVE-1
JAMIA NAGAR, OKHLA, NEW DELHI-25
GST NO. 07AGQPR8379H1ZG

Subject: - Service Order for BOQ for sheeting Work.

Dear Sir,

We are pleased to place our order for following works as per rate as below-

S.No.	Description	Qty	Rate	Amount
01.	Removing of Existing ACC roofing sheets i/c Ridges, Screws and other hardwares and staking of useable materials and disposed of unserviceable materials within site as directed by BST. (Only Plan area shall be measured)	10000 Sqm	70/-	7,00,000/-
02.	Fixing of 0.5 mm Thick (TCT) Trim Deck Bare GALVALUME profile sheet. The end rib shall be designed for anti-capillary action, to avoid any seepage of water through the lateral overlap. The feed material is manufactured out of nominal 0.47 mm Base Metal Thickness (BMT), Hi-Tensile steel with min. 550 MPa yield strength, metallic hot dip coated with Aluminium-Zinc alloy (55% Aluminium, 45% Zinc) as per AS 1397 - Zincalume AZ150 (Min. 150 gms/sq.mt total on both sides). It shall include cost of Metal sheet Hex head self drilling screws(EJOT Make) meeting DIN EN ISO 9277 & 50018 having 25 micron zinc alloy coating with AZ 150 GSM 0.8 mm Thick metal Bonded EDPM washer. (Only laid area shall be measured). (sheet and other hardware in BST scope) Self Screw Provide by M/s: Aala Technocrat	10000 Sqm	115/-	11,50,000/-
03.	Fixing of End/cap/corner Flashings made of Galvalume materials with AZ 150 Coating as per above material specifications.	250 RMT	60/-	15,000/-
04.	Fixing of 13 mm thick XLPE insulation with both side Aluminium Foil/lamination as per Manufacturer's specification i/c cost of 100 GSM coated GI mesh of 75x75 x1.5 mm and Welding Mesh 100x100x2mm Supplied by M/s: Aala Technocrat	10000 Sqm	100/-	10,00,000/-
IGST 18%		Taxable Value		28,65,000/-
				5,15,700/-
		Total Amount		33,80,700/-



Date: - 07.12.2022



## BST Textile Mills Pvt. Ltd.

## Terms & Condition:-

- 01. Payment: 20% advance along with order & 60% payment to be paid with progress of work & balance 20% after successfully & completion of the work or Final payment will be done after total measurement.
- 02. Starting Time and completion: work will be started after 15 days of the order confirmation/advance payment or within 1-2 days after received the material at our site and the whole work has to be completed as soon as possible.

03. We will provide accommodation of your workers and supervisors at our site.

Thanking You

For BST Textile Mills Put Ltd

FOR EST TEXTILE MILLS PVT LTD

Authorized Signatory

AND SKYLMAN