



# AJEX INDUSTRIES

Head Office : 407, Ground Floor, Double Storey, Welcome Seelampur-III, New Delhi - 110053

Corporate Off : G-121, MG ROAD, INDUSTRIAL AREA, PHASE-1, HAPUR (M.NO.: 91-9313356085)

Ref. No. 87/Hiss/2017

Dated 20/08/2017

## Quotation

**Buyer's Name:** M/s HISS PETROCHEM PVT. LTD.  
**Address:** Vill & Post Rohta Road, Rohta, Meerut**Name of state:** Uttar Pradesh  
**GSTIN:** 09AADCH9886M1ZL**Place of Supply:** Meerut**Consignee's Name:** AJEX INDUSTRIES**Address:** 407, Ground Floor, Double Storey,  
Welcome Seelampur-III, New Delhi- 110053**Name of state:** Uttar Pradesh  
**GSTIN:** 07DZUPK0585A1Z7

Dear Sir,

With reference to above as well as verbal discussion had with your honour, we are submitting our possible estimate for the same. Short details are here under:-

1. Complete Fabrication & supply of 1No. 3 MT. Capacity Grease cooking kettle (Made of 8 mm MS. Plate for shell and 22 mm for Bottom Plate) along with its agitator paddles fixed/Moving, 3" dia Bright shaft, GM Bush housing, Thrust bearing MS Colour. Top cover Plate 6 mm thick, 200×100 joist for gear box/Motor chair, 4 Nos. 200×100 Joist for Joist Coloum, steel Jacketed Furnace, fire bricks, Fire clay, Glass wool, Hard Setting Powder, 6" dia vappour chimney, 10 "dia Fire chimney 60-0" in height, 8' C/D Reduction gear Box, 15 HP, Electric Motor directly coupled, Nut Bolt etc.

Rs. 14,74,577/-

2. Complete Fabrication & supply of 1No. 6 MT. Capacity Grease cooking kettle (Made of 8 mm thick MS. Plate for shell and 6 mm thick MS. Plate for Water Jacket) along with its agitator, Scraper, 3×3 SQ shaft, GM Bush housing, Thrust bearing MS Colowe, 4 mm thick MS. Plates for Top cover Plate, 200×100 joist for gear box/Motor chair, 4 Nos. 200×100 Joist Coloum, 8' C/D Reduction gear Box, 15 HP, Electric Motor, Nut Bolt etc.

Rs. 11,77,967/-

3. Complete Fabrication & supply of 1No. 6 MT. Capacity Grease holding kettle (Made of 8 mm thick MS. Plate) along with its agitator, Scraper, 3×3 SQ shaft, GM Bush housing, Thrust bearing MS Colowe 4 mm thick Top cover Plate, 200×100 joist for gear box/Motor chair, 4 Nos. 200×100 Joist Coloum, 8' C/D Reduction gear Box, 15 HP Electric Motor, Nut Bolt etc.

Rs. 11,35,594/-



# AJEX INDUSTRIES

Head Office : 407, Ground Floor, Double Storey, Welcome Seelampur-III, New Delhi - 110053

Corporate Off : G-121, MG ROAD, INDUSTRIAL AREA, PHASE-1, HAPUR (M.NO.: 91-9313356085)

Ref. No. 87/Hiss/2017

Dated 20/08/2017

4. Supply of 1No. Moore house miling machine directly fitted with 15 HP Flange Mounted vertical 3000 RPM Electric Motor, Stone adjusting hand wheel and a set of Grinding stone etc.  
Rs. 3,00,846/-
5. Supply of 1No. Hopper-cum-deaerator along with 1NO. 3"×3" Force Pump, 1 No. 7.5 HP Electric Motor, 'V' Pully, 'V' Belt fitted on a Angle iron Frame.  
Rs. 2,24,575/-
6. Supply of 1No. 500 litre capacity sump tank, made from 3mm thick MS. Plate with Angle Ring.  
Rs. 29,660/-
7. (a) Supply of 3Nos. 3"×3" Rotary Gear Pump with 7.5 HP. 'V' Pully, 'V' Belt fitted on Angle iron Frame.  
Rs. 3,09,320/-  
(b) Supply of 1No. 2"×2" Rotary Gear Pump with 3 HP. Motor directly coupled fitted on a base frame.  
Rs. 59,325/-
8. Supply of 1No. stacker (Barrel lifter 4'-0"×14'-0" in height along with ½ "Q wire rope with wire rope drum, 3"C/D reduction gear box. 2 HP Motor directly coupled, ½" Pitch chain with chain sprocket etc.  
Rs. 2,54,240/-
9. Supply of 2Nos. Barrel lifting and shifting hand trolley.  
Rs. 59,320/-
10. Supply of 1 lot 2" and 3" dia pipe line from sump tank to Grease cooking kettle, cooking kettle to grease cooking kettle, cooling kettle to holding kettle and to Moore house miling machine too.  
Rs. 2,79,662/-



# AJEX INDUSTRIES

Head Office : 407, Ground Floor, Double Storey, Welcome Seelampur-III, New Delhi - 110053

Corporate Off : G-121, MG ROAD, INDUSTRIAL AREA, PHASE-1, HAPUR (M.NO.: 91-9313356085)

Ref. No. 87/Hiss/2017

Dated 20/08/2017

11. Supply of 1 No. wesman heating/ pumping unit with 5 HP Electric blower with 3 A Burner.

Rs. 3,05,085/-

12. Supply of 2 Nos. 50KL Capacity vertical Oil storage tank, tank made of 10 mm thick plate for bottom, 6 mm plate for shell and top plate along with its 500 dia manhole with over plate, inlet and outlet nipple with flange and vent nozzle too.

Rs. 16,52,540/-

13. Installation charges above plant at your site.

Rs. 2,96,610/-

14. Commissioning charges of the above plant.

Rs. 67,797/-

**Total Assessable Value**

Rs. 76,27,118/-

**Add: C.G.S.T. @ 9%**

Rs. 6,86,441/-

**Add: S.G.S.T. @ 9%**

Rs. 6,86,441/-

**Total**

Rs. 90,00,000/-

(In Words: Ninety Lacs Only)

Yours Faithfully

For AJEX INDUSTRIES