

(L & B) MSP

Total 21,678.23

Account Code	Place	Description	Type of Construction	Measurement (L*B*H) (meters)	Gross Block	Date of Capitalisation	Year
AA104	Sponge Iron Plant	Crushing House Shed (For Coal)	AC sheet roofing RCC foundation, MS joist column with angle bracings.	8 m*5 m*16m, (4 floors) - 2 Nos.	11.60	Dec-05	2005
AA104	Sponge Iron Plant	Ground Hopper Shed (For Coal)	AC sheet roofing RCC foundation, MS joist column with angle bracings.	5 m*5 m*4 m*4 m (depth) & 3 m*25 m*4 m (inclination) - 2 Nos.	9.00	Dec-05	2005
AA104	Sponge Iron Plant	Ground Hopper Shed (For Iron Ore)	AC sheet roofing RCC foundation, MS joist column with angle bracings.	5 m*5 m*4 m*4 m (depth) & 3 m*25 m*4 m (inclination) - 2 Nos.	6.00	Dec-05	2005
AA104	Sponge Iron Plant	Iron Ore Fines Stock Bin and Hopper	AC sheet roofing RCC foundation, MS joist	8 m*4 m*15m - 2 Nos.	1.92	Dec-05	2005
AA104	Sponge Iron Plant	Iron Ore Screen House	AC sheet roofing RCC foundation, MS joist	6 m*5 m*12m - 2 nos. (3 floors)	5.40	Dec-05	2005
AA104	Sponge Iron Plant	Coal Transfer House	AC sheet roofing RCC foundation, MS joist	4 m*4 m*8 m (2 floors) - 2 Nos.	1.92	Dec-05	2005
AA104	Sponge Iron Plant	Feed Bunker Shed	AC sheet roofing RCC foundation, MS joist column with angle bracings.	6 m*50 m*12-22 m (in different portion) - 2 nos.	28.00	Dec-05	2005
AA104	Sponge Iron Plant	After Burning Chamber	AC sheet roofing RCC foundation, MS joist	8m*8m*40m (9 floor) - 2 nos.	47.50	Dec-05	2005
AA104	Sponge Iron Plant	Kiln Feed Building	AC sheet roofing RCC foundation, MS joist	8m*6m*25m (5 floor) - 2 nos.	22.40	Dec-05	2005
AA104	Sponge Iron Plant	Kiln Cooler Transfer Building	AC sheet roofing RCC foundation, MS joist	10m*10m*20m (4 floor) - 2 nos.	26.00	Dec-05	2005
AA104	Sponge Iron Plant	Cooler Discharge House	AC sheet roofing RCC foundation, MS joist column with angle bracings.	6 m*12 m*5 m*5 m (depth) & 6 m*15 m*5 m (inclination) - 3 nos.	9.72	Dec-05	2005
AA104	Sponge Iron Plant	Product House Transfer Building	AC sheet roofing RCC foundation, MS joist	8m*8m*20m - 2 nos.	3.84	Dec-05	2005
AA104	Sponge Iron Plant	Product House With Stock Bins	AC sheet roofing RCC foundation, MS joist	12m*12m*15-24m (5 floor) - 3 nos.	101.80	Dec-05	2005
AA104	Sponge Iron Plant	Underground Reservoir	RCC underground construction with 250 mm thick wall being 5 meter deep. Finish with water proofing compound and CI manhole covers.	12 m * 30 m * 5 m (with suitable partitions)	7.06	Dec-05	2005
AA104	Sponge Iron Plant	Overhead Reservoir	RCC construction with 250mm thick concrete wall.		3.00	Dec-05	2005
AA104	Sponge Iron Plant	Padestal for Kiln & Cooler	RCC foundation with 6 m Depth	750 Cu m of RCC to carry a load of 1200 MT	68.50	Dec-05	2005
AA104	Sponge Iron Plant	Cooler Tray and Drainage	RCC construction	40m*10m*2m depth	3.00	Dec-05	2005
AA104	Sponge Iron Plant	Electric control room and D.G. Set room.	RCC roof slab, 250 mm thick brick wall with cement plasters, steel windows, wooden door and water proof floors.	12 m *6 m *2 m (2 Nos.)	4.32	Dec-05	2005
AA104	Sponge Iron Plant	Laboratory	RCC structure, 250 mm thick brick wall, RCC roof slab, plaster finish.	15 m *10 m *3 m	4.50	Dec-05	2005
AA104	Sponge Iron Plant	Administrative Building	RCC structure, RCC roofing with 250 mm thick wall, wooden doors, windows, MS grill, terezzo floor finish with sanitary pises and fittings.	20 m *10 m *3 m (2 floors)	32.40	Dec-05	2005
AA104	Sponge Iron Plant	Stuff Quarters	AC sheet roofing RCC foundation, MS joist	30 m *10 m *3 m (2 floors)	46.10	Dec-05	2005
AA104	Sponge Iron Plant	Toilets	RCC structure, 450 mm thick brick wall, RCC roof complete with piping and sanitary fittings.	L.S.	8.50	Dec-05	2005
AA104	Sponge Iron Plant	Security Room	RCC foundation, RCC roof slab, 450 mm thick brick wall with cement plaster, steel windows & wooden doors.	L.S.	7.30	Dec-05	2005
AA104	Sponge Iron Plant	Guest House	Guest House in the Plant	16100 SQFT	130.77	Dec-05	2005
AA104	Re-Rolling Mill	Main factory shed (Mill Shed) Including Shed	AC sheet roofing RCC foundation, steel column	146m' x 20m'	71.32	Mar-06	2006
AA104	Re-Rolling Mill	Workshop /Panel/Furnace Pump Room	AC sheet roofing RCC foundation, MS joist column with angle bracings.	45m' x 8m'	8.56	Mar-06	2006
AA104	Re-Rolling Mill	Electric sub-station Room	RCC foundation, 10" thick wall with concrete roofing	12mX6m	1.51	Mar-06	2006
AA104	Re-Rolling Mill	Labour Quarter	AC sheet roofing RCC foundation, MS joist column with angle bracings.	30mx 15m	15.58	Mar-06	2006
AA104	Re-Rolling Mill	Under Ground Water Reservoir	Concrete wall, Cement finish	L.S.	7.00	Mar-06	2006
AA104	Re-Rolling Mill	Overhead Water Tank		L.S.	5.00	Mar-06	2006
AA104	Re-Rolling Mill	Furnace Oil Tank	Concrete wall, Steel Tank	L.S.	3.00	Mar-06	2006
AA104	Re-Rolling Mill	Overhead Oil Service Tank	Steel Tank	L.S.	1.00	Mar-06	2006
AA104	Re-Rolling Mill	Deep TubeWell			1.50	Mar-06	2006
AA104	Re-Rolling Mill	Furnace Shed		24mx10m	8.04	Mar-06	2006
AA104	Billet Plant	Main Factory Shed	RCC foundation, AC sheet roofing, MS joist column with angle bracing.	150 x 21 x 16	120.25	Dec-05	2005
AA104	Billet Plant	Lean-to-shed	AC sheet roofing RCC foundation, MS joist column with angle bracings.	55 x 13 x 8	15.73	Dec-05	2005
AA104	Billet Plant	Furnace Room	250 mm thick reinforced concrete about 1500 mm below ground level with RCC beams (250 x 400 mm) are to be casted at ground and Intel level. Furnace room wall crucible foundation and roof slab will be 250 mm thick.		13.25	Dec-05	2005
AA104	Billet Plant	Store Room (2 Floors)	RCC frame structure building, RCC roof with 250 mm brick work alongwith rolling shutter, steel windows and cement finish.	10 x 30	15.50	Dec-05	2005
AA104	Billet Plant	Scrap Bay		110 x 20	49.00	Dec-05	2005
AA104	Billet Plant	Billet Bay		70 x 22	35.80	Dec-05	2005
AA104	Billet Plant	R. Table Bay		22 x 11	4.36	Dec-05	2005

	Billet Plant	Underground Reservoir	RCC underground construction		22.00	Dec-05	2005
AA104	Billet Plant	Main plant building	RCC foundation, AC sheet, roofing, MS joist column	60 X 21 X 20	98.20	Dec-05	2005
AA104	Billet Plant	Scrap Bay / Billet Storage Bay	AC sheet roofing RCC foundation, MS joist column with angle bracings.	60 X 21 X 14	90.60	Dec-05	2005
AA104	Billet Plant	IF Platform & Control underneath	RCC	26 X 13 X 4	30.21	Dec-05	2005
AA104	Billet Plant	IF Transformer & Breaker Room	Brick building with roof		16.44	Dec-05	2005
AA104	Billet Plant	Pump house for Induction furnace ,CCM , etc	AC sheet roofing RCC foundation, MS joist column with angle bracings.	40 X 8 X 3.5	24.40	Dec-05	2005
AA104	Billet Plant	LRF Transformer , auxiliary & control room	AC sheet roofing RCC foundation, MS joist column with angle bracings.		4.50	Dec-05	2005
AA104	Billet Plant	LRF operating Platform	RCC	12 X 10 X 4.1	5.40	Dec-05	2005
AA104	Billet Plant	Cold Sumps, Hot Sumps, etc	RCC	50 X 5.5 X 3	37.00	Dec-05	2005
AA104	Billet Plant	Compressor Room	Bricks building with RC roof	6 X 5 X 3.5	1.35	Dec-05	2005
AA104	Billet Plant	Pollution Control Chimney			5.00	Dec-05	2005
AA104	Billet Plant	Converter Foundation			10.00	Dec-05	2005
AA104	Billet Plant	Work Shop Shed		10 X 10 X 3.5	4.50	Dec-05	2005
AA104	Billet Plant	Weighbridge foundation			10.00	Dec-05	2005
AA104	Captive Power Plant	Building	Complete civil works including structural work, Plate works.		321.71	Jun-06	2006
AA104	Common Facilities	Building	Complete civil works including structural work, Plate works.		135.50	Oct-06	2006
AA104	Common Facilities	Building	Complete civil works including structural work, Plate works.		7.61	Mar-09	2009
AA104	Pellet Plant	Drying room	RCC trestle frame	360 Sq.Mt.	37.33	Jan-09	2009
AA104	Pellet Plant	Ore grinding room	RCC trestle frame	550 Sq.Mt.	57.04	Jan-09	2009
AA104	Pellet Plant	Concentrate warehouse	RCC trestle frame	1600 Sq.Mt.	165.92	Jan-09	2009
AA104	Pellet Plant	Bentonite warehouse	RCC trestle frame	200 Sq.Mt.	20.74	Jan-09	2009
AA104	Pellet Plant	Mixing building	RCC trestle frame	350 Sq.Mt.	36.30	Jan-09	2009
AA104	Pellet Plant	Junction house	RCC trestle frame	75 Sq.Mt.	7.78	Jan-09	2009
AA104	Pellet Plant	Junction house	RCC trestle frame	75 Sq.Mt.	7.78	Jan-09	2009
AA104	Pellet Plant	Junction house	RCC trestle frame	140 Sq.Mt.	14.52	Jan-09	2009
AA104	Pellet Plant	Pelletization room	RCC trestle frame	800 Sq.Mt.	82.96	Jan-09	2009
AA104	Pellet Plant	Chain grate room	RCC trestle frame	1500 Sq.Mt.	155.55	Jan-09	2009
AA104	Pellet Plant	Substation	RCC trestle frame	320 Sq.Mt.	33.18	Jan-09	2009
AA104	Pellet Plant	Main control room	Mixed brick	100 Sq.Mt.	10.37	Jan-09	2009
AA104	Pellet Plant	Belt corridor	Light steel	75 Sq.Mt.	7.78	Jan-09	2009
AA104	Pellet Plant	Product yard	mixed brick	2160 Sq.Mt.	223.99	Jan-09	2009
AA104	Pellet Plant	Deduster platform	RCC platform, light steel rainproof hood	100 Sq.Mt.	10.37	Jan-09	2009
AA104	Pellet Plant	Concentrate bin	RCC	40 Sq.Mt.	4.15	Jan-09	2009
AA104	Pellet Plant	Return fines bin	RCC	50 Sq.Mt.	5.19	Jan-09	2009
AA104	Pellet Plant	Chimney	steel	150 T	15.56	Jan-09	2009
AA104	Pellet Plant	Circulate pump house	RCC	180 Sq.Mt.	18.67	Jan-09	2009
AA104	Pellet Plant	Cold water pool	RCC	50 Sq.Mt.	5.19	Jan-09	2009
AA104	Pellet Plant	Pipeline support	RCC	75 Sq.Mt.	7.78	Jan-09	2009
AA104	Pellet Plant	Foundation of chain grate	RCC	125 Sq.Mt.	12.96	Jan-09	2009
AA104	Pellet Plant	Foundation of rotary kiln	RCC	250 Sq.Mt.	25.93	Jan-09	2009
AA104	Pellet Plant	Foundation of pellet machine	RCC	225 Sq.Mt.	30.96	Jan-09	2009
AA104	Pellet Plant	Foundations of drying machine, blender mixer etc.	RCC	325 Sq.Mt.	34.17	Jan-09	2009
AA104	Coal Washery (Old)	Raw Coal Receiving Dump Hopper and Tunnel	RCC/Steel Structure	37.5 Sq.Mt.	2.58	Jan-06	2006
AA104	Coal Washery (Old)	Primary Crusher House and Foundation	Concrete/RCC Steel Structure	12.5 Sq.Mt.	3.73	Jan-06	2006
AA104	Coal Washery (Old)	Secondary Crusher House and Foundation	Concrete/RCC Steel Structure	12.5 Sq.Mt.	4.26	Jan-06	2006
AA104	Coal Washery (Old)	Junction Houses	Concrete/RCC Steel Structure	7.5 Sq.Mt.	2.67	Jan-06	2006
AA104	Coal Washery (Old)	Raw Coal Surge Hopper	Concrete/RCC Steel Structure	5 Sq.Mt.	2.78	Jan-06	2006
AA104	Coal Washery (Old)	Washery Building	Concrete/RCC Steel Structure	475 Sq.Mt.	106.63	Jan-06	2006
AA104	Coal Washery (Old)	Thickener	RCC	107.5 Sq.Mt.	4.30	Jan-06	2006
AA104	Coal Washery (Old)	Electric Building and Control Room	RCC/Steel Structure	50 Sq.Mt.	2.54	Jan-06	2006
AA104	Coal Washery (Old)	Water Reservoir	RCC	105 Sq.Mt.	4.20	Jan-06	2006
AA104	Coal Washery (Old)	Conveyor Galleries	Concrete/RCC Steel Structure	500 Sq.Mt.	112.25	Jan-06	2006
AA104	Coal Washery (Old)	Bunker for Clink Coal, Middling & Rejects	Concrete/RCC Steel Structure	20 Sq.Mt.	9.40	Jan-06	2006
AA104	Coal Washery (Old)	Road and Workmen Building	Different Types	50 Sq.Mt.	2.00	Jan-06	2006

	Coal Washery (Old)	Crushed raw Coal Storage	RCC/ Steel Structure	30 Sq.ML	10.88	Jan-06	2006
04	Coal Washery (Old)	Borewell			2.50	Jan-06	2006
AA104	RMHS	For Clean Coal - Twin Shed	Civil Works	260 Cum	18.20	Mar-10	2010
		For Clean Coal - Twin Shed	RCC works				
AA104	RMHS	For Clean Coal - Twin Shed	Structural steel works	190 MT	76.00	Mar-10	2010
		For Iron Ore -Single Shed					
AA104	RMHS	For Iron Ore -Single Shed	Civil Works	285 Cum	19.95	Mar-10	2010
		For Iron Ore -Single Shed	RCC works				
AA104	RMHS	For Iron Ore -Single Shed	Structural steel works	195 MT	73.75	Mar-10	2010
		Modification of existing coal shed including extension , construction of new shed					
AA104	RMHS	Modification of existing coal shed including extension , construction of new shed	Civil Works	412 Cum	21.98	Mar-10	2010
		Modification of existing coal shed including extension , construction of new shed	RCC works				
AA104	RMHS	Modification of existing coal shed including extension , construction of new shed	Structural steel works	215 MT	86.00	Mar-10	2010
AA104	RMHS	Belt Press Materials and middlings - Power Plant	Civil Works	250 Cum	14.98	Mar-10	2010
		Belt Press Materials and middlings - Power Plant	RCC works				
AA104	RMHS	Belt Press Materials and middlings - Power Plant	Structural steel works	219 MT	91.16	Mar-10	2010
AA104	Structural Rolling Mill	Clean Coal - Twin Shed	Civil Works - RCC works	260 Cum	17.59	Apr-10	2010
AA104	Structural Rolling Mill	Clean Coal - Twin Shed	Structural steel works	275 MT	106.34	Apr-10	2010
AA104	Structural Rolling Mill	Iron Ore -Single Shed	Civil Works - RCC works	285 Cum	19.29	Apr-10	2010
AA104	Structural Rolling Mill	Iron Ore -Single Shed	Structural steel works	300 MT	116.01	Apr-10	2010
AA104	Structural Rolling Mill	Modification of existing coal shed including extension , construction of new shed	Civil Works - RCC works	500 Cum	33.84	Apr-10	2010
AA104	Structural Rolling Mill	Modification of existing coal shed including extension , construction of new shed	Structural steel works	515 MT	199.15	Apr-10	2010
AA104	Structural Rolling Mill	Belt Press Materials and middlings - Power Plant	Civil Works - RCC works	450 Cum	30.45	Apr-10	2010
AA104	Structural Rolling Mill	Belt Press Materials and middlings - Power Plant	Structural steel works	614 MT	247.48	Apr-10	2010
AA104	DRI Plant	Civil & Structural Work	EXCAVATION	6098.1 M3	2.25	Jan-11	2011
AA104	DRI Plant	Civil & Structural Work	PCC	246.85 M3	1.29	Jan-11	2011
AA104	DRI Plant	Civil & Structural Work	SHUTTERING	9099.52 M2	9.47	Jan-11	2011
AA104	DRI Plant	Civil & Structural Work	RCC	5065.02 M3	195.63	Jan-11	2011
AA104	DRI Plant	Civil & Structural Work	STEEL INSERT	13.05 MT	2.85	Jan-11	2011
AA104	DRI Plant	Civil & Structural Work	BOLTS INSERTS	8830.02 Kg	2.22	Jan-11	2011
AA104	DRI Plant	Civil & Structural Work	BACK FILLING	3493.02 M3	0.70	Jan-11	2011
AA104	DRI Plant	Civil & Structural Work	BRICK WORK	415.4 M3	3.49	Jan-11	2011
AA104	DRI Plant	Civil & Structural Work	POCKET SHUTRING	297.6 M2	0.35	Jan-11	2011
AA104	DRI Plant	Civil & Structural Work	WATER PROOF PLASTERING	2449.2 M2	1.28	Jan-11	2011
AA104	DRI Plant	Civil & Structural Work	STRUCTURAL STEEL	2500 MT	646.54	Jan-11	2011
AA104	DRI Plant	Civil & Structural Work	CHIMNEY		58.78	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	Excavation	3500 Cu.M	3.31	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	Backfilling with Approved Earth	2700 Cu.M	1.92	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	P.C.C.	50 Cu.M	1.18	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	RCC Grade M 25 in columns, beams, upper floor, etc.	800 Cu.M	34.07	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	Reinforcement	80 T	37.86	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	Brickwork	500 Cu.M	9.46	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	Windows, Doors etc.	260 Sq.M	3.94	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	Plastering	6250 Sq.M	3.55	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	Flooring	1400 Sq.M	3.97	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	Painting	4200 Sq.M	2.38	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	Structural Steel	50 T	28.39	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	Grating	50 Sq.M	0.66	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	Plumbing	LS	1.89	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	Sheeting for Roof Coverage	500 Sq.M	9.46	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	False Flooring	50 Sq.M	1.42	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	False Ceiling	50 Sq.M	0.95	Jan-11	2011
AA104	18 mw Power Plant	Power Plant Building	Roof Treatment : Foam Conc. And Tar Tarfelting	1600 Sq.M	9.84	Jan-11	2011

	18 mw Power Plant	Power Plant Building	Rain Water Gutter & Drain Pipes	LS	0.95	Jan-11	2011
	18 mw Power Plant	Foundation for Boilers, Turbo-Generator, Pumps & Other Equipment	Excavation	6000 Cu.M	5.68	Jan-11	2011
AA104	18 mw Power Plant	Foundation for Boilers, Turbo-Generator, Pumps & Other Equipment	Backfilling with Approved Earth	2000 Cu.M	1.42	Jan-11	2011
AA104	18 mw Power Plant	Foundation for Boilers, Turbo-Generator, Pumps & Other Equipment	P.C.C.	200 Cu.M	4.73	Jan-11	2011
AA104	18 mw Power Plant	Foundation for Boilers, Turbo-Generator, Pumps & Other Equipment	RCC grade M 25 including Formwork	1500 Cu.M	63.88	Jan-11	2011
AA104	18 mw Power Plant	Foundation for Boilers, Turbo-Generator, Pumps & Other Equipment	Reinforcement Steel	150 T	70.98	Jan-11	2011
AA104	18 mw Power Plant	Foundation for Boilers, Turbo-Generator, Pumps & Other Equipment	Miscellaneous (Embedments, Foundations etc.)	LS	4.73	Jan-11	2011
AA104	18 mw Power Plant	Ash Silo & Miscellaneous Foundations	Excavation	500 Cu.M	0.47	Jan-11	2011
AA104	18 mw Power Plant	Ash Silo & Miscellaneous Foundations	Backfilling with Approved Earth	250 Cu.M	0.18	Jan-11	2011
AA104	18 mw Power Plant	Ash Silo & Miscellaneous Foundations	P.C.C.	70 Cu.M	1.66	Jan-11	2011
AA104	18 mw Power Plant	Ash Silo & Miscellaneous Foundations	RCC Grade M 20 including Formwork	350 Cu.M	14.91	Jan-11	2011
AA104	18 mw Power Plant	Ash Silo & Miscellaneous Foundations	Reinforcement	35 T	16.56	Jan-11	2011
AA104	18 mw Power Plant	RCC CHIMNEY(FOR AFBC ONLY)	Excavation	160 Cu.M	0.15	Jan-11	2011
AA104	18 mw Power Plant	RCC CHIMNEY(FOR AFBC ONLY)	Backfilling with Approved Earth	100 Cu.M	0.07	Jan-11	2011
AA104	18 mw Power Plant	RCC CHIMNEY(FOR AFBC ONLY)	P.C.C.	50 Cu.M	1.18	Jan-11	2011
AA104	18 mw Power Plant	RCC CHIMNEY(FOR AFBC ONLY)	RCC Grade M 25 including Formwork	300 Cu.M	12.78	Jan-11	2011
AA104	18 mw Power Plant	RCC CHIMNEY(FOR AFBC ONLY)	Reinforcement	10 T	4.73	Jan-11	2011
AA104	18 mw Power Plant	RCC work (M-20) in miscellaneous equipment foundation,cable trench etc (Including Reinforcement)	ID Fan	50 Cu.M	4.50	Jan-11	2011
AA104	18 mw Power Plant	RCC work (M-20) in miscellaneous equipment foundation,cable trench etc (Including Reinforcement)	Transformer Foundation	50 Cu.M	4.50	Jan-11	2011
AA104	18 mw Power Plant	RCC work (M-20) in miscellaneous equipment foundation,cable trench etc (Including Reinforcement)	Ducts and trestles	35 Cu.M	3.15	Jan-11	2011
AA104	18 mw Power Plant	RCC work (M-20) in miscellaneous equipment foundation,cable trench etc (Including Reinforcement)	Cable Trench	1000 Cu.M	89.91	Jan-11	2011
AA104	18 mw Power Plant	RCC work (M-20) in miscellaneous equipment foundation,cable trench etc (Including Reinforcement)	Miscellaneous Equipment: (Comp: 22;BFP,CEP,D)	397 Cu.M	35.69	Jan-11	2011
AA104	18 mw Power Plant	Culverts and drains		150 Cu.M	13.49	Jan-11	2011
AA104	18 mw Power Plant	Steel Work in Miscellaneous Structures	Ash Handling system	50 T	28.39	Jan-11	2011
AA104	18 mw Power Plant	Steel Work in Miscellaneous Structures	Pipe Trestle	30 T	17.04	Jan-11	2011
AA104	18 mw Power Plant	Steel Work in Miscellaneous Structures	Misc Buildings: Compressor House,DM Plant etc	20 T	11.36	Jan-11	2011
AA104	18 mw Power Plant	CW Pump House, CW pump Foundation/Misc Pumps		LS	0.95	Jan-11	2011
AA104	18 mw Power Plant	Civil cost:Foundation and CW basin /sump for cooling tower/ Air cooled condenser & Cooling Tower	Civil Cost	LS	23.66	Jan-11	2011
AA104	18 mw Power Plant	Civil cost:Foundation and CW basin /sump for cooling tower/ Air cooled condenser & Cooling Tower	PCC	80 Cu.M	1.89	Jan-11	2011
AA104	18 mw Power Plant	Civil cost:Foundation and CW basin /sump for cooling tower/ Air cooled condenser & Cooling Tower	RCC including Reinforcement and form work	800 Cu.M	71.93	Jan-11	2011
AA104	18 mw Power Plant	Raw Water Reservoir	Administration Building	LS	5.00	Jan-11	2011
AA104	18 mw Power Plant	Raw Water Reservoir	DG Shed, Stores, Technical Room	LS	2.00	Jan-11	2011
AA104	18 mw Power Plant	Raw Water Reservoir	Canteen & Cycle Shed	LS	1.99	Jan-11	2011
AA104	18 mw Power Plant	Raw Water Reservoir	Borewells & Piping and Valves for connection up	LS	0.47	Jan-11	2011
AA104	18 mw Power Plant	Raw Water Reservoir	Pavement, Greenery Development	LS	2.37	Jan-11	2011
AA104	18 mw Power Plant	Raw Water Reservoir	Workshop, Time Office and Laboratory	LS	2.37	Jan-11	2011
AA104	18 mw Power Plant	Raw Water Reservoir	Miscellaneous Works	LS	4.73	Jan-11	2011
AA104	Coal Washery (New)	Civil Work (RCC work including buildings, MCC, control room)	Structural steel work of 1050 MT	1500 M3	218.05	Mar-12	2012
AA104	Coal Washery (New)	Common Facilities			19.38	Mar-12	2012
AA104	Coal Washery (New)	Coal Shed	Civil Works with Structural steel work of 1000 MT	1000 M3	209.76	Mar-12	2012
AA104	Coal Washery (New)	Civil Work	Raw Material Handling System		59.66	Mar-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Burdening	500 Cum	67.98	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Dryer	250 Cum	43.26	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Granulation	950 Cum	104.44	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Travelling Grate	1350 Cum	183.54	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Kiln	400 Cum	60.56	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Cooler	1250 Cum	188.48	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Transfer House 1	80 Cum	27.56	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Transfer House 2	70 Cum	23.73	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Mixture Building	80 Cum	27.56	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Duct & Duct Support	200 Cum	200.22	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Conveyor	400 Cum	134.72	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	PCI Main Building	250 Cum	103.51	Jun-12	2012

AA104	Pellet Plant (New)	Pellet Civil Work	PCI Shed	400 Cum	130.08	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	ESP	220 Cum	71.93	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	ID Fan	160 Cum	14.95	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Chimney	550 Cum	43.88	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Pump House	300 Cum	28.43	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Water Tank	200 Cum	14.83	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Muticloners	220 Cum	62.66	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	HRFan	130 Cum	12.73	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Product House & Screen	600 Cum	100.11	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Road	2000 Cum	148.31	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Drainage	800 Cum	59.33	Jun-12	2012
AA104	Pellet Plant (New)	Pellet Civil Work	Miscellaneous	1000 Cum	135.95	Jun-12	2012
AA104	Pellet Plant (New)	Benification Plant - Civil Work	Ground Hopper , open area for Iron ore stocking	1150 Cum	123.90	Jun-12	2012
AA104	Pellet Plant (New)	Benification Plant - Civil Work	Stacking & Reclaiming	500 Cum	222.47	Jun-12	2012
AA104	Pellet Plant (New)	Benification Plant - Civil Work	Dat bin	600 Cum	59.94	Jun-12	2012
AA104	Pellet Plant (New)	Benification Plant - Civil Work	Benification Building	4500 Cum	501.51	Jun-12	2012
AA104	Pellet Plant (New)	Benification Plant - Civil Work	Concentrate shed	400 Cum	122.36	Jun-12	2012
AA104	Pellet Plant (New)	Benification Plant - Civil Work	Thickner	1500 Cum	126.68	Jun-12	2012
AA104	Pellet Plant (New)	Benification Plant - Civil Work	Pump House	300 Cum	31.52	Jun-12	2012
AA104	Pellet Plant (New)	Benification Plant - Civil Work	Tailing filter Room	350 Cum	56.85	Jun-12	2012
AA104	Pellet Plant (New)	Benification Plant - Civil Work	Conveyer system	500 Cum	160.67	Jun-12	2012
AA104	Pellet Plant (New)	Benification Plant - Civil Work	Misc. Buildings	1100 Cum	279.18	Jun-12	2012
AA104	34 MW Power Plant	Power Plant Building	Excavation	7000 Cu.M	7.45	Jun-12	2012
AA104	34 MW Power Plant	Power Plant Building	Backfilling with Approved Earth	2500 Cu.M	1.99	Jun-12	2012
AA104	34 MW Power Plant	Power Plant Building	P.C.C.	100 Cu.M	2.66	Jun-12	2012
AA104	34 MW Power Plant	Power Plant Building	RCC Grade M 25 in foundation,Column,beams, u	2500 Cu.M	119.66	Jun-12	2012
AA104	34 MW Power Plant	Power Plant Building	Reinforcement	300 T	159.55	Jun-12	2012
AA104	34 MW Power Plant	Power Plant Building	Brickwork for cladding and partition wall	965 Cu.M	20.53	Jun-12	2012
AA104	34 MW Power Plant	Power Plant Building	Side clading with .0550 mm TCT Lloyddeck perma	Sq.m		Jun-12	2012
AA104	34 MW Power Plant	Power Plant Building	Doors and windows	400 Sq.M	6.81	Jun-12	2012
AA104	34 MW Power Plant	Power Plant Building	Plastering	10000 Sq.M	6.38	Jun-12	2012
AA104	34 MW Power Plant	Flooring	Ironite	2100 Sq.M	6.70	Jun-12	2012
AA104	34 MW Power Plant	Flooring	Mosaic	200 Sq.M	0.85	Jun-12	2012
AA104	34 MW Power Plant	Flooring	Painting	7200 Sq.M	4.74	Jun-12	2012
AA104	34 MW Power Plant	Flooring	Structural Steel	300 T	147.25	Jun-12	2012
AA104	34 MW Power Plant	Flooring	Grating	50 Sq.M	0.74	Jun-12	2012
AA104	34 MW Power Plant	Flooring	Plumbing	LS	2.13	Jun-12	2012
AA104	34 MW Power Plant	Flooring	Sheeting for Roof Coverage	720 Sq.M	15.32	Jun-12	2012
AA104	34 MW Power Plant	Flooring	False Flooring	200 Sq.M	6.38	Jun-12	2012
AA104	34 MW Power Plant	Flooring	False Ceiling	200 Sq.M	4.25	Jun-12	2012
AA104	34 MW Power Plant	Roof Treatment : Foam Conc. And Tarfelting	Foam Concrete,Tarfelting	300 Sq.M	2.07	Jun-12	2012
AA104	34 MW Power Plant	Roof Treatment : Foam Conc. And Tarfelting	Rain Water Gutter & Drain Pipes	LS	2.13	Jun-12	2012
AA104	34 MW Power Plant	Foundation for Boilers, Turbo-Generator, Pumps & Other Equipment Including Cooling Tower	Excavation	10000 Cu.M	10.64	Jun-12	2012
AA104	34 MW Power Plant	Foundation for Boilers, Turbo-Generator, Pumps & Other Equipment Including Cooling Tower	Backfilling with Approved Earth	4000 Cu.M	2.13	Jun-12	2012
AA104	34 MW Power Plant	Foundation for Boilers, Turbo-Generator, Pumps & Other Equipment Including Cooling Tower	P.C.C.	200 Cu.M	5.32	Jun-12	2012
AA104	34 MW Power Plant	Foundation for Boilers, Turbo-Generator, Pumps & Other Equipment Including Cooling Tower	RCC grade M 25 including Formwork	4000 Cu.M	191.46	Jun-12	2012
AA104	34 MW Power Plant	Foundation for Boilers, Turbo-Generator, Pumps & Other Equipment Including Cooling Tower	Reinforcement Steel	400 T	212.73	Jun-12	2012
AA104	34 MW Power Plant	Foundation for Boilers, Turbo-Generator, Pumps & Other Equipment Including Cooling Tower	Miscellaneous (Embedments, Foundations etc.)	LS	8.51	Jun-12	2012
AA104	34 MW Power Plant	Ash Silo & Coal Handling & Miscellaneous Foundations	Excavation	1000 Cu.M	1.06	Jun-12	2012
AA104	34 MW Power Plant	Ash Silo & Coal Handling & Miscellaneous Foundations	Backfilling with Approved Earth	500 Cu.M	0.40	Jun-12	2012
AA104	34 MW Power Plant	Ash Silo & Coal Handling & Miscellaneous Foundations	P.C.C.	70 Cu.M	1.86	Jun-12	2012
AA104	34 MW Power Plant	Ash Silo & Coal Handling & Miscellaneous Foundations	RCC Grade M 25 including Formwork	700 Cu.M	33.51	Jun-12	2012
AA104	34 MW Power Plant	Ash Silo & Coal Handling & Miscellaneous Foundations	Reinforcement	70 T	37.23	Jun-12	2012
AA104	34 MW Power Plant	Chimney Foundation(For CFBC only)	Excavation	1000 Cu.M	1.06	Jun-12	2012

AA104	34 MW Power Plant	Chimney Foundation(For CFBC only)	Backfilling with Approved Earth	300 Cu.M	0.24	Jun-12	2012
AA104	34 MW Power Plant	Chimney Foundation(For CFBC only)	P.C.C.	10 Cu.M	0.27	Jun-12	2012
AA104	34 MW Power Plant	Chimney Foundation(For CFBC only)	RCC Grade M 25Including Formwork	800 Cu.M	38.29	Jun-12	2012
AA104	34 MW Power Plant	Chimney Foundation(For CFBC only)	Reinforcement	50 T	26.59	Jun-12	2012
AA104	34 MW Power Plant	RCC work (M-25) in miscellaneous equipment fondation,cable trench etc(Including Reinforcement)	ID,FD,PA Fans	400 Cu.M		Jun-12	2012
AA104	34 MW Power Plant	RCC work (M-25) in miscellaneous equipment fondation,cable trench etc(Including Reinforcement)	Transformer Foundation	75 Cu.M	7.58	Jun-12	2012
AA104	34 MW Power Plant	RCC work (M-25) in miscellaneous equipment fondation,cable trench etc(Including Reinforcement)	Ducts and trestles	50 Cu.M	5.05	Jun-12	2012
AA104	34 MW Power Plant	RCC work (M-25) in miscellaneous equipment fondation,cable trench etc(Including Reinforcement)	Cable Trench	200 Cu.M	20.21	Jun-12	2012
AA104	34 MW Power Plant	RCC work (M-25) in miscellaneous equipment fondation,cable trench etc(Including Reinforcement)	Miscellaneous Equipment: (Comp: 30,BFP,CEP, .	500 Cu.M	50.52	Jun-12	2012
AA104	34 MW Power Plant	Culverts and drains: RCC M20	Steel Work in Miscellaneous Structures	100 Cu.M	10.10	Jun-12	2012
AA104	34 MW Power Plant	Culverts and drains: RCC M20	Ash Handling system	100 T	63.82	Jun-12	2012
AA104	34 MW Power Plant	Culverts and drains: RCC M20	Pipe Trestle	100 T	63.82	Jun-12	2012
AA104	34 MW Power Plant	Culverts and drains: RCC M20	Misc Buildings: Compressor House,DM Plant etc	100 T	63.82	Jun-12	2012
AA104	34 MW Power Plant	CW Pump House, CW pump Foundation	Excavation	1000 CUM	1.06	Jun-12	2012
AA104	34 MW Power Plant	CW Pump House, CW pump Foundation	Backfilling with Approved Earth	300 CUM	0.16	Jun-12	2012
AA104	34 MW Power Plant	CW Pump House, CW pump Foundation	P.C.C.	40 CUM	1.06	Jun-12	2012
AA104	34 MW Power Plant	CW Pump House, CW pump Foundation	RCC Grade M 25 including Formwork	500 CUM	23.93	Jun-12	2012
AA104	34 MW Power Plant	CW Pump House, CW pump Foundation	Reinforcement	10 T	5.32	Jun-12	2012
AA104	34 MW Power Plant	CW Pump House, CW pump Foundation	CW Piping	300 T	159.55	Jun-12	2012
AA104	34 MW Power Plant	Raw Water Reservoir: (10 days storage @225 cum/hr 5m deep)	(i)Excavation	55000 CUM	58.50	Jun-12	2012
AA104	34 MW Power Plant	Raw Water Reservoir: (10 days storage @225 cum/hr 5m deep)	(ii)Slide protection with 200 mm thick M20 RCC	7000 CUM	297.83	Jun-12	2012
AA104	34 MW Power Plant	Raw Water Reservoir: (10 days storage @225 cum/hr 5m deep)	(iii) Pump Platform, Pump House etc M25 RCC	250 CUM	25.26	Jun-12	2012
AA104	34 MW Power Plant	Coal Handling Plant	Excavation	800 Cu.M	0.85	Jun-12	2012
AA104	34 MW Power Plant	Coal Handling Plant	Backfilling with Approved Earth	300 Cu.M	0.24	Jun-12	2012
AA104	34 MW Power Plant	Coal Handling Plant	P.C.C.	10 Cu.M	0.27	Jun-12	2012
AA104	34 MW Power Plant	Coal Handling Plant	RCC Grade M 25Including Formwork	500 Cu.M	23.93	Jun-12	2012
AA104	34 MW Power Plant	Coal Handling Plant	Reinforcement	50 T	26.59	Jun-12	2012
AA104	34 MW Power Plant	Coal Handling Plant	Steel Structure	1000 Ton	425.47	Jun-12	2012
AA104	34 MW Power Plant	Coal Handling Plant	Administration Building		212.73	Jun-12	2012
AA104	34 MW Power Plant	Coal Handling Plant	DG Shed, Stores, Technical Room	LS	2.66	Jun-12	2012
AA104	34 MW Power Plant	Coal Handling Plant	Canteen & Cycle Shed		2.66	Jun-12	2012
AA104	34 MW Power Plant	Coal Handling Plant	Pavement, Greenery Development	LS	5.32	Jun-12	2012
AA104	34 MW Power Plant	Coal Handling Plant	Workshop, Time Office and Laboratory	LS	5.32	Jun-12	2012
AA104	34 MW Power Plant	Coal Handling Plant	Miscellaneous Works	LS	5.32	Jun-12	2012
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Excavation of soft medium soil upto depth of 3m including de-watering of pit etc complete	216 cum	1.63	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Providing & laying in situ,cement concrete M-10 / (1;3;6) of trap/granite/quartzite/gneiss metal for foundation and bedding including plywood/steel formwork,bailing out water,compacting,finishing uneven and honey combed surface curine etc complete	14.8 cum	2.27	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Filling of murum in layers including ramming & watering complete	72 cum	0.35	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Filling boulders with 40% murum including watering and ramming etc complete	180 cum	2.60	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Providing & casting reinforced cement concrete in 1;1;5;3 mix for RCC required for Columns,beams, slabs, lintels, chls, lofts, etc with 3/4" gauge metal including plywood / steel formwork,centerine,curine etc complete.	340.66 cum	78.62	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Providing bending, binding and laying in position MS reinforcement of all sizes including the cost of binding wire etc complete.	19.65 ton	28.34	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Providing & laying 230 thk II class burnt brick masonry in C.M.1;5 including watering etc, complete.	292.4 cum	27.90	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Providing & laying 115 thk 1st class burnt brick masonry in C.M.1;3 including RCC coping 75 thk at every 1200 M including watering etc complete.	432.8 sqm	7.49	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Providing & fixing 1st class quality teak wood doors with fully panelled shutter 1.5"thk as per design with TW frame of 2.5"x5" including necessary fixtures etc complete.	32 no	5.40	Jan-11	2011

AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Providing & fixing prelaminated hard core flush door panels 1.5"thk with TW frame of 2.5"x5" including necessary fixtures etc complete.	96 no	9.37	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Cement Plaster in 1:6 to ceiling including curing etc. complete [INTERNAL]	947.7 sqm	5.26	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Cement Plaster in 1:6 to walls including curing etc. complete [INTERNAL]	1505.44 sqm	8.02	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Providing and fixing designer ceramic tiles 1'x1' in bedroom and kitchen in neat cement mortar with fitting, cleaning, etc. complete	947.7 sqm	13.58	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Providing and fixing designer glazed ceramic tiles on floor and wall upto 7' height in toilet in neat cement mortar with fitting, cleaning, etc. complete	312.15 sqm	15.87	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Providing and applying plastic emulsion paint of approved colour on ceiling with all surface preparation & cement based putty base finish etc. complete	947.7 sqm	4.98	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Providing and applying plastic emulsion / lusture paint of approved colour on internal walls with all surface preparation & cement based outty base finish etc. complete	1505.44 sqm	10.40	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Applying double coat plain cement plaster of 1:6 mix with phanti and curing etc complete.[EXTERNAL]	118.5 sqm	0.87	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Applying double coat sand face cement plaster 1:2 over 1:4 mix with sandy texture using punch machine including water-proofing liquid, curing etc. complete.[EXTERNAL]	762.1 sqm	7.61	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Providing and applying 2 coats of external acrylic based weather proofing paint (apex or equivalent) of approved colour on external walls with texture finish etc. complete.	880.6 sqm	3.79	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Plumbing: Providing and laying all GI pipe lines (Concealed) for water supply with all tap fittings with testing etc. complete and installation of all sanitary fixtures with all accessories & Providing and laying all CI pipes for sewage and waste water drain	43.67	Jan-11	2011	
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Electrification: Providing and laying concealed flexible copper wiring in heavy duty PVC conduits with modular switch with all DBs, MCBs, ELCBs with installation of entire lighting fixtures, lamps, fans with proper testing etc. complete.	48.64	Jan-11	2011	
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type D	Providing and fixing mild steel glazed windows - as per colour approved with glazing, including fittings, fixtures etc complete.	133.77 sqm	7.01	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Excavation of soft medium soil upto depth of 3m including de-watering of pit etc complete	198 cum	3.60	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Providing & laying in situ, cement concrete M-10 / (1:1.5:6) of trap/granite/quartzite/gneiss metal for foundation and bedding including plywood/steel formwork, balling out water, compacting, finishing uneven and honey combed surface curing etc. complete.	12.2 cum	4.51	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Filling of murum in layers including ramming & watering complete	68.5 cum	0.81	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Filling boulders with 40% murum including watering and ramming etc complete	162.2 cum	5.64	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Providing & casting reinforced cement concrete in 1:1.5:3 mix for RCC required for Columns, beams, slabs, lintels, chills, lofts, etc with 3/4" gauge metal including plywood / steel formwork, centerline curing etc complete.	312.24 cum	167.09	Apr-10	2010
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Providing bending, binding and laying in position MS reinforcement of all sizes including the cost of binding wire etc complete.	15.4 ton	53.58	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Providing & laying 230 thk II class burnt brick masonry in C.M.1:6 including watering etc. complete.	233.4 cum	53.72	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Providing & laying 115 thk 1st class burnt brick masonry in C.M.1:3 including RCC coping 75 thk at every 1200 mm including watering etc complete.	330.12 sqm	13.78	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Providing & fixing 1st class quality teak wood doors with fully panelled shutter 1.5"thk as per design with TW frame of 2.5"x5" including necessary fixtures etc complete.	24 no	9.76	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Providing & fixing prelaminated hard core flush door panels 1.5"thk with TW frame of 2.5"x5" including necessary fixtures etc complete.	84 no	19.78	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Cement Plaster in 1:6 to ceiling including curing etc. complete [INTERNAL]	820.5 sqm	10.98	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Cement Plaster in 1:6 to walls including curing etc. complete [INTERNAL]	1410.8 sqm	18.12	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Providing and fixing designer ceramic tiles 1'x1' in bedroom and kitchen in neat cement mortar with fitting, cleaning, etc. complete	820.5 sqm	28.36	Jan-11	2011

AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Providing and fixing designer glazed ceramic tiles on floor and wall upto 7' height in toilet in neat cement mortar with fitting, cleaning, etc. complete	288.5 sqm	35.37	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Providing and applying plastic emulsion paint of approved colour on ceiling with all surface preparation & cement based putty base finish etc. complete	820.5 sqm	10.40	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Providing and applying plastic emulsion / lusture paint of approved colour on internal walls with all surface preparation & cement based putty base finish etc. complete	1410.8 sqm	23.51	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Applying double coat plain cement plaster of 1:6 mix with phantli and curing etc. complete. [EXTERNAL]	102.3 sqm	1.81	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Applying double coat sand face cement plaster 1:2 over 1:4 mix with sandy texture using punch machine including water-proofing liquid, curing etc. complete. [EXTERNAL]	710.4 sqm	17.11	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Providing and applying 2 coats of external acrylic based weather proofing paint (apex or equivalent) of approved colour on external walls with texture finish etc. complete.	812.7 sqm	8.43	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Plumbing: Providing and laying all GI pipe lines (Concealed) for water supply with all tap fittings with testing etc. complete and installation of all sanitary fixtures with all accessories & Providing and laying all CI pipes for sewage and waste water etc.	71.93		Apr-10	2010
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Electrification: Providing and laying concealed flexible copper wiring in heavy duty PVC conduits with modular switches with all DBs, MCBs, ELCBs with installation of entire lighting fixtures, lamps, fans with proper testing etc. complete.	86.92		Apr-10	2010
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Providing and fixing mild steel glazed windows - as per colour approved with glazing, including fittings, fixtures etc complete.	110.2 sqm	13.92	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type C	Excavation of soft medium soil upto depth of 3m including de-watering of pit etc complete	110 cum	1.50	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Providing & laying in situ, cement concrete M-10 / (1:3:6) of trap/granite/quartzite/gneiss metal for foundation and bedding including plywood/steel formwork, bailing out water, compacting, finishing uneven and honey combed surface, curing etc. complete.	7.3 cum	2.01	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Filling of murum in layers including ramming & watering complete	38.4 cum	0.34	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Filling boulders with 40% murum including watering and ramming etc complete	96.2 cum	2.50	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Providing & casting reinforced cement concrete in 1:1.5:3 mix for RCC required for Columns, beams, slabs, lintels, chills, lofts, etc with 3/4" gauge metal including plywood / steel formwork, centering, curing etc complete.	160.24 cum	73.38	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Providing bending, binding and laying in position MS reinforcement of all sizes including the cost of binding wire etc complete.	10.3 ton	26.78	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Providing & laying 230 thk II class burnt brick masonry in C.M. 1:6 including watering etc, complete.	140.2 cum	24.11	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Providing & laying 115 thk 1st class burnt brick masonry in C.M. 1:3 including RCC coping 75 thk at every 1200 M. Including watering etc complete.	186.4 sqm	5.82	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Providing & fixing 1st class quality teak wood doors with fully panelled shutter 1.5" thk as per design with TW frame of 2.5"x5" including necessary fixtures etc complete.	8 no	2.43	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Providing & fixing prelaminated hard core flush door panels 1.5" thk with TW frame of 2.5"x5" including necessary fixtures etc complete.	32 no	5.63	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Cement Plaster in 1:6 to ceiling including curing etc. complete [INTERNAL]	492.4 sqm	4.92	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Cement Plaster in 1:6 to walls including curing etc. complete [INTERNAL]	1410.8 sqm	13.54	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Providing and fixing designer ceramic tiles 1'x1' in bedroom and kitchen in neat cement mortar with fitting, cleaning, etc. complete	492.4 sqm	12.72	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Providing and fixing designer glazed ceramic tiles on floor and wall upto 7' height in toilet in neat cement mortar with fitting, cleaning, etc. complete	178.9 sqm	16.39	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Providing and applying plastic emulsion paint of approved colour on ceiling with all surface preparation & cement based putty base finish etc. complete	492.4 sqm	4.66	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Providing and applying plastic emulsion / lusture paint of approved colour on internal walls with all surface preparation & cement based putty base finish etc. complete	804.1 sqm	10.02	Jan-11	2011

	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Applying double coat plain cement plaster of 1:6 mix with phanti and curing etc complete.[EXTERNAL]	58.5 sqm	0.77	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Applying double coat sand face cement plaster 1:2 over 1:4 mix with sandy texture using punch machine including water-proofing liquid, curing etc. complete.[EXTERNAL]	373.6 sqm	6.72	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Providing and applying 2 coats of external acrylic based weather proofing paint (apex or equivalent) of approved colour on external walls with texture finish etc. complete.	260.5 sqm	2.02	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Plumbing: Providing and laying all GI pipe lines (Concealed) for water supply with all tap fittings with testing etc. complete and Installation of all sanitary fixtures with all accessories & Providing and laying all CI pipes for sewage and waste water drain		29.48	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Electrification: Providing and laying concealed flexible copper wiring in heavy duty PVC conduits with modular switch with all DBs, MCBs, ELCBs with installation of entire lighting fixtures, lamps, fans with proper testing etc. complete.		34.56	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION - Type B	Providing and fixing mild steel glazed windows - as per colour approved with glazing, including fittings, fixtures etc complete.	78.9 sqm,	7.45	Jan-11	2011
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION	Civil works for TYPE C Buildings		321.60	Nov-13	2013
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION	✓ Engineers Hostel (Bachelor)		401.40	Nov-13	2013
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION	Community Centre		47.54	Nov-13	2013
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION	✓ School with Administrative Block		408.96	Nov-13	2013
AA104	MSP Colony	BUILDINGS & CIVIL CONSTRUCTION	Labour Colony Building		489.98	Nov-13	2013
AA104	MSP Colony	ROADS	✓ Work External - High way to main gate		54.43	Nov-13	2013
AA104	MSP Colony	ROADS	Bitumenous Road Work External - Railway siding to Bridge near Batching Plant		378.56	Nov-13	2013
AA104	MSP Colony	ROADS	Bitumenous Road Work External - Batching Turning to Pellet Plant Main Gate (B) 8 M wide & 3640 M long.		109.58	Nov-13	2013
AA104	MSP Colony	ROADS	Bitumenous Road Work - 34 MV near PGP via Stock Yard to Road crossing meeting (C) 7 M wide & 520 M long.		43.50	Nov-13	2013
AA104	MSP Colony	ROADS	STREET LIGHTING ALONG MSP ROAD 3.0 KM		119.91	Nov-13	2013
AA104	Common Facilities	Construction of Housing Colony & Internal & External Road	Street lighting along MSP Road 3.0 km, Work External - High way to main gate, Bitumenous Road Work External - Railway siding to Bridge near Batching Plant, Batching Turning to Pellet Plant Main Gate (B) 8 M wide & 3640 M long, 34 MV near PGP via Stock Yard to Road crossing meeting (C) 7 M wide & 520 M long.		1,231.81	Nov-13	2013
AA104	Common Facilities	Layout marking, Earth Work, Excavation, Dressing & Shifting of soil	Preparation of Ash Pond.	Area of land 50 Acre X 5 Mts depth=50X4400 sqm X 5 m depth=11,00,000 cum @Rs 100 per cum	1,169.25	Aug-14	2014
AA104	Common Facilities	Iron Ore Shed with RCC Flooring, Side Walls, etc.	Miscellaneous	15000 sqm	1,587.35	Aug-14	2014
AA104	Common Facilities	Iron Ore Shed with RCC Flooring, Side Walls, etc.	Miscellaneous	SMS Unit	356.34	Aug-14	2014
AA104	Common Facilities	Building & Civil Works	Miscellaneous		963.00	Mar-15	2015