

13

# SHIVALIK ELEVATORS

(A Company with Complete Solutions for Vertical Transportation)

P.C Tower, Office No.-201, Above SBI Bank of India, Mamura, Sector-66, Noida, U.P.

E-mail: shivalikelevators@gmail.com; info@shivalikelevators.com; mohit@shivalikelevators.com;

www.shivalikelevators.com

Ref No .....

Date 22/01/2024

TO,

Mr. Sunil Kumar

GSTN : 05AIAPV2398C1ZA

Client site Address: , Plot No-70, Sector -7,IIE , Sidcul Haridwar -249493

Sir,

We thank you very for enquiry about requirement of goods lifts.

We are maintaining our very competitive and reasonable rate here under.

The lift is meant for Goods .

## • TECHNICAL DETAILS OF CONTER WEIGHT GOODS LIFT

• Safe working load	1000kg
• No. of stoppage	B+G+3 landing
• Machine	Sharp
• Safty	OSG
• Drive	Invt
• Door	Collapsible Door
• Guide Rail Car	9 mm ,6mm

- Wire rope 13 mm (Usha martin)
- Platform size 1200\*900 mm
- Speed 0.5 mm
- Opening 1000\*2000 mm Opening
- Car Cabin MS powder coating finish

Total amount Rs 15,00,000 ,fifteen Lakh only  
 GST 18% Extra ,Quantity (2) goods Lift

---

### ***ELECTRICAL &SAFTY DETAILS***

---

CONTROL	:	110V DC SUPPLY
PUSH BOTTON BOX	:	PUSH BOTTON BOX INDICATER
	:	SHOW THE MOMENT OF THE LIFTS SS PLATE            DISPLAY
Control penal	:	Drive Base
Wire	:	SHIVALIK
SAFETY	:	FACE PREVANTER
	:	GATE LOCK SAFTY
	:	U.F.C (UP FINAL CUT)
	:	D.F.C (DOWN FINAL CUT BUFFER SPRING

# ***TERMS & CONDITIONS***

---

## **WARRANTY**

We Provide twelve Months Warrantee

- The payment shall be making as mentioned below:
- 20% Advance at the time of confirmation of order.
- 60% Against delivery- second stage Material .
- 15% Against delivery all material.
- 05% balance on final handing over.

### **Notes:**

- The above prices excluded of taxes, however any statutory variation shall be to your account.
- The legal possession of the lift will transfer to you only when full payment is made as per the above agreement.
- The order once placed will not be refund in any case.
- The advance will not be refund in any case.

**NOTE** : **WITH Part One' YEAR WARRENTY**



**CIVIL AND ELECTRICAL WORK ARE PROVIDE BY OWNER**

All civil work, scaffolding, template, 3 phase electric supply at machine room and single-phase electric supply in lift shaft and MCD/DDA permission and works mentioned in the other copies shall be to your account.

3 PHASE 4-wire cable 6Sq.mm copper/alum with 63 amp MCCB or ELCB.  
and double earthing of 14 SWG copper wire 415VAC +OR~  
10%@50HZ+OR~3%

16AMP MCCB For lift lighting with ISI mark.

16AMP MCCB for machine room & lift shaft lighting with ISI mark.

One plug point and one bulb holder with switches in the lift shaft on each floor.

(A) Lighting points in the M/C room with two switches.

(B) Plug point in the M/C room with one switch. (C) Exhaust fan point with one switch.

(D) Electrical caution board two no's (F) C,channel & scup folding

### TERMS OF DELIVERY

We hand over you the elevators in 180 days after the confirmation of order with 20% advance of 1 payment. we delivered all material are guild rails, brackets, 60% Against delivery- second stage Material. car frame counter frame, machine rope and cabin car door landing doors and controllers wiring material in 40-45 days install after 15% of against all material the handover of elevators 40-45 days relies 05% balance payment in 1 week all the days are counting depends on the receiving of payments

On behalf of Purchaser

Name : Mr Sunil Kumar

Authorized Signatory

On behalf of shivalik Elevators

Mohit Singh

Authorized Signatory