

5. “Group Housing Project” at Plot No.- 4B, Sector- 12, Greater Noida (West), District- Gautam Buddh Naga, Shri Rajesh Jain, M/s Grand Realtech Limited., File No. 7664/7615/ Proposal No. SIA/UP/INFRA2/419343/2023

The consultant informed the committee that they are strictly following the rules, regulations and other instructions of QCI/NABET. A presentation was made by the project proponent along with their consultant M/s EQMS India Pvt. Ltd. Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged:

1. The environmental clearance is sought for “Group Housing Project” at Plot No.- 4B, Sector- 12, Greater Noida (West), District- Gautam Buddh Nagar, U.P., M/s Grand Realtech Limited.
2. The standard terms of reference in the matter were issued through online Parivesh Portal on 24/06/2023. EIA report submitted by the project proponent on 23/02/2023.
3. The proposed housing complex will comprise of Dwelling Units (3BHK+2T, 3BHK+3T and 4BHK+3T) in 10 Towers, community center comprising of maximum B+S+24 Floors along with basic civic infrastructure facilities such as water, sanitation, sewerage/seepages, road, electricity along with necessary social/commercial infrastructure for residents.
4. Area details:

S. No.	Particulars	Unit	Details
AREA DETAILS			
1	Plot Area	m ²	30,000
2	Podium Area		15205.542
3	Ground Coverage (Permissible) – 35%	m ²	10,500
4	Total Ground Coverage (Proposed) – 28.56%	m ²	8570.628
5	F.A.R (Permissible)		
a	F.A.R (Permissible) – 3.5	m ²	105,000
b	Additional FAR (IGBC: 5% of permissible FAR)- 0.175	m ²	5,250
c	Total Permissible FAR – 3.675	m ²	110,250
d	Permissible Commercial FAR (1% of 3.5 FAR)	m ²	1,050
e	Net Permissible Residential FAR	m ²	109,200
6	FAR proposed – 3.675	m ²	110,248.844
a	Residential FAR	m ²	109,199.410
b	Commercial FAR	m ²	1,049.434
7	Permissible Ancillary Area (15% of 3.5 FAR)	m ²	15,750
8	Proposed Ancillary area	m ²	15,749.00
9	Basement Area	m ²	26,871.251
10	Total Non-FAR area Including Basement	m ²	43,791.44
11	Built-up Area (FAR+ NON-FAR+ Basement Area+ Ancillary area)	m ²	169,789.28
12	Green Area (37.81%)	m ²	11343.69 sqm (9118.30 sq. m at stilt/podium i.e. 30% of the plot area and 2225.39 sq. m at ground level i.e. 7.41% of total plot area)

5. Land use details:

Particular	Area (Sqm)	Percentage
Ground Coverage	8570.628	28.56876
Green Area at Ground	2225.39	7.417966667
Surface Parking Area	1168.13	3.893766667
Roads, Open and other area	18035.852	60.11950667
Total Plot Area (A)	30000	100

6. Green area details:

S. No.	Particulars	Details
1.	Total Green Area	11343.69 sq.m
2.	%age of total plot area	9118.30 sqm at stilt/podium i.e., 30% of the plot area at stilt/podium and 2225.39 sqm at ground level i.e., 7.41% of total plot area at

		ground level.
3.	Total of No. of Trees to be cut	0
4.	Total No. of Trees required to be planted	Total Plot Area/80 = 375
5.	Total No. of Trees proposed to be planted	375
6.	Timeline for Completion of Plantation	1 years

7. Parking details:

Parking Required			
Particular	Norms		ECS
Parking Required for Commercial	FAR achieved/ 50 sqm	1050/50	21
Parking Required for Residential	FAR achieved/ 80 sqm	103950/80	1300
Total Parking Required			1321
Parking Provision			
Location	Area	Standard	ECS
Basement Parking	20606.42	30/18	725
Stilt Area	15515.66	30	517
Open Area/ Surface Parking	1668.13	20	83
Total Parking Provided			1325

4. Water requirement details:

S. No.	Particulars	Quantity	Factor	Total Water Requirement (LPCD)	Domestic Requirement (LPCD)	Flushing Requirement (LPCD)	Waste water (LPCD)
1	Residential						
	3BHK + 2T	1728	135	233280	155520	77760	
	3 BHK + 3T	3456	135	466560	311040	155520	
	4 BHK + 3T	864	135	116640	77760	38880	
	Staff	303	45	13635	7575	6060	
	Visitors	605	15	9072	3024	6048	
2	Community	796	-	14340	5580	8760	
	Fixed	80	45	3600	2000	1600	
	Floating	716	15	10740	3580	7160	
3	Stilt Shops	350	-	6300	2450	3850	
	Fixed	35	45	1575	875	700	
	Floating	315	15	4725	1575	3150	
	Sub Total			859827	562949	296878	0
	Wastewater				450359.2	296878	747237.2
4	Filter Backwash			20000			20000
5	Swimming Pool			10000			2000
6	Landscaping	11343.69 m2	4 Lt/sqm	40000			
	Total Water (Litters)			929827	562949	296878	769237.2
	Total Water (KLD)			~929.827 KLD	~562.949 KLD	~296.878 KLD	~769.237 KLD

5. Solid waste details:

S. No	Particulars	Capacity	Standard- Kg/day	Total Waste- Kg/day	Biodegradable Kg/day	Non Biodegradable- Kg/day
Domestic Waste						
1	3 BHK+2T	1728	0.5	864	518.4	345.6
2	3BHK+3T	3456	0.5	1728	1036.8	691.2
3	4 BHK+3 T	864	0.5	432	259.2	172.8
4	Staff	303	0.3	90.9	54.54	36.36
5	Visitors	605	0.15	90.72	54.432	36.288
6	Stilt Shops	350	0.15	52.5	31.5	21
	Total Municipal Waste			3258	1955	1303

6. 16 nos. of rain water harvesting pits provided in the project.

7. The maximum power demand load of the project will be 3986 KVA while the connected load will be 7477 KVA. Source of Power Supply will be NPCL (Noida Power Company Limited). DG set of capacity 1 x 750 kVA, 2 x 500 kVA will be installed at ground level in open to sky area with appropriate stack height as per CPCB norms to for power backup during power failure.
8. The project proposal falls under category-8(a) of EIA Notification, 2006 (as amended).

The consultant (EIA Coordinator) also submitted an affidavit dated 24/03/2023 mentioning is as follows:

1. I, Sweta Shah, D/o Kaushikray S Shah is EIA Coordinator of M/s EQMS India Pvt. Ltd.
2. I have prepared EIA/EMP report for the "Group Housing Project" at Plot No.- 4B, Sector- 12, Greater Noida (West), District- Gautam Buddh Nagar, U.P., M/s Grand Realtech Limited with my team.
3. I have personally visited the site of proposal and certify that no construction activity has been undertaken on the project site for the present proposal.
4. I have satisfied with that all the necessary data/information submitted along with EIA are true and correct.
5. I certify that this project proposal has been uploaded for the first time on Parivesh Portal.
6. I certify that there is no mismatch between information/data provided on the online application submitted on Parivash Portal and hard copy which is submitted after acceptance of application.
7. I state that all the TOR Points have been complied in EIA report.
8. The report for the Proposal will be prepared by my team as per guideline laid down by QCI/NABET.

RESOLUTION AGAINST AGENDA NO. 05

The committee discussed the matter and recommended grant of environmental clearance on the proposal as above alongwith standard environmental clearance conditions prescribed by MoEF&CC, GoI and following additional conditions:

Additional Conditions:

1. Project proponent is advised to explore the possibility and getting the cement in a closed container rather through the plastic bag to prevent dust emissions at the time of loading/unloading.
2. Project proponent should ensure that there will be no use of "Single use of Plastic" (SUP).
3. In compliance to Hon'ble Supreme Court order dated 13/01/2020 in IA no. 158128/2019 and 158129/2019 in Writ petition no. 13029/1985 (MC Mehta Vs. GoI and others) anti-smog guns shall be installed to reduce dust during excavation.
4. The proponent should provide the sufficient electric vehicle charging points as per the requirements at ground level and allocate the safe and suitable place in the premises for the same.
5. Proponent shall comply with the action plan and CSR plan submitted by PP/consultant at the time of EIA presentation.
6. Project proponent should adopt the 01 village and development them as model village.

Standard Environmental Clearance Conditions prescribed by MoEF&CC:

1. Statutory compliance:
 1. The project proponent shall obtain all necessary clearance/ permission from all relevant agencies including town planning authority before commencement of work. All the construction shall be done in accordance with the local building byelaws.
 2. The approval of the Competent Authority shall be obtained for structural safety of buildings due to earthquakes, adequacy of firefighting equipment etc as per National Building Code including protection measures from lightning etc.
 3. The project proponent shall obtain forest clearance under the provisions of Forest (Conservation) Act, 1986, in case of the diversion of forest land for non-forest purpose involved in the project.

4. The project proponent shall obtain clearance from the National Board for Wildlife, if applicable.
5. The project proponent shall obtain Consent to Establish / Operate under the provisions of Air (Prevention & Control of Pollution) Act, 1981 and the Water (Prevention & Control of Pollution) Act, 1974 from the concerned State Pollution Control Board/ Committee.
6. The project proponent shall obtain the necessary permission for drawl of ground water / surface water required for the project from the competent authority.
7. A certificate of adequacy of available power from the agency supplying power to the project along with the load allowed for the project should be obtained.
8. All other statutory clearances such as the approvals for storage of diesel from Chief Controller of Explosives, Fire Department, Civil Aviation Department shall be obtained, as applicable, by project proponents from the respective competent authorities.
9. The provisions of the Solid Waste (Management) Rules, 2016, e-Waste (Management) Rules, 2016, and the Plastics Waste (Management) Rules, 2016 shall be followed.
10. The project proponent shall follow the ECBC/ECBC-R prescribed by Bureau of Energy Efficiency, Ministry of Power strictly.
2. Air quality monitoring and preservation:
 1. Notification GSR 94(E) dated 25.01.2018 of MoEF&CC regarding Mandatory Implementation of Dust Mitigation Measures for Construction and Demolition Activities for projects requiring Environmental Clearance shall be complied with.
 2. A management plan shall be drawn up and implemented to contain the current exceedance in ambient air quality at the site.
 3. The project proponent shall install system to carryout Ambient Air Quality monitoring for common/criterion parameters relevant to the main pollutants released (e.g. PM10 and PM25) covering upwind and downwind directions during the construction period.
 4. Construction site shall be adequately barricaded before the construction begins. Dust, smoke & other air pollution prevention measures shall be provided for the building as well as the site. These measures shall include screens for the building under construction, continuous dust/ wind breaking walls all around the site (at least 3 meter height). Plastic/tarpaulin sheet covers shall be provided for vehicles bringing in sand, cement, murram and other construction materials prone to causing dust pollution at the site as well as taking out debris from the site.
 5. Sand, murram, loose soil, cement, stored on site shall be covered adequately so as to prevent dust pollution.
 6. Wet jet shall be provided for grinding and stone cutting.
 7. Unpaved surfaces and loose soil shall be adequately sprinkled with water to suppress dust.
 8. All construction and demolition debris shall be stored at the site (and not dumped on the roads or open spaces outside) before they are properly disposed. All demolition and construction waste shall be managed as per the provisions of the Construction and Demolition Waste Rules 2016.
 9. The diesel generator sets to be used during construction phase shall be low sulphur diesel type and shall conform to Environmental (Protection) prescribed for air and noise mission standards.
 10. The gaseous emissions from DG set shall be dispersed through adequate stack height as per CPCB standards. Acoustic enclosure shall be provided to the DG sets to mitigate the noise pollution. The location of the DG set and exhaust pipe height shall be as per the provisions of the Central Pollution Control Board (CPCB) norms.
 11. For indoor air quality the ventilation provisions as per National Building Code of India.
3. Water quality monitoring and preservation:
 1. The natural drain system should be maintained for ensuring unrestricted flow of water. No construction shall be allowed to obstruct the natural drainage through the site, on wetland and water bodies. Check dams, bio-swailes, landscape, and other sustainable urban drainage systems (SUDS) are allowed for maintaining the drainage pattern and to harvest rain water.
 2. Buildings shall be designed to follow the natural topography as much as possible. Minimum cutting and filling should be done.
 3. Total fresh water use shall not exceed the proposed requirement as provided in the project details.

4. The quantity of fresh water usage, water recycling and rainwater harvesting shall be measured and recorded to monitor the water balance as projected by the project proponent. The record shall be submitted to the Regional Office, MoEF&CC along with six monthly Monitoring reports.
5. A certificate shall be obtained from the local body supplying water, specifying the total annual water availability with the local authority, the quantity of water already committed, the quantity of water allotted to the project under consideration and the balance water available. This should be specified separately for ground water and surface water sources, ensuring that there is no impact on other users.
6. At least 20% of the open spaces as required by the local building bye-laws shall be pervious. Use of Grass pavers, paver blocks with at least 50% opening, landscape etc. would be considered as pervious surface.
7. Installation of dual pipe plumbing for supplying fresh water for drinking, cooking and bathing etc and other for supply of recycled water for flushing, landscape irrigation car washing, thermal cooling, conditioning etc. shall be done.
8. Use of water saving devices/ fixtures (viz. low flow flushing systems; use of low flow faucets tap aerators etc) for water conservation shall be incorporated in the building plan.
9. Use of water saving devices/ fixtures (viz. low flow flushing systems; use of low flow faucets tap aerators etc) for water conservation shall be incorporated in the building plan.
10. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices referred.
11. The local bye-law provisions on rain water harvesting should be followed. If local byelaw provision is not available, adequate provision for storage and recharge should be followed as per the Ministry of Urban Development Model Building Byelaws, 2016. Rain water harvesting recharge pits/storage tanks shall be provided for ground water recharging as per the CGWB norms.
12. A rain water harvesting plan needs to be designed where the recharge bores of minimum one recharge bore per 5,000 square meters of built up area and storage capacity of minimum one day of total fresh water requirement shall be provided. In areas where ground water recharge is not feasible, the rain water should be harvested and stored for reuse. The ground water shall not be withdrawn without approval from the Competent Authority.
13. All recharge should be limited to shallow aquifer.
14. No ground water shall be used during construction phase of the project.
15. Any ground water dewatering should be properly managed and shall conform to the a approvals and the guidelines of the CGWA in the matter. Formal approval shall be taken from the CGWA for any ground water abstraction or dewatering.
16. The quantity of fresh water usage, water recycling and rainwater harvesting shall be measured and recorded to monitor the water balance as projected by the project proponent. The record shall be submitted to the Regional Office, MoEF&CC along with six monthly Monitoring reports.
17. Sewage shall be treated in the STP with tertiary treatment. The treated effluent from STP shall be recycled/re-used for flushing, AC make up water and gardening. As proposed, not related water shall be disposed in to municipal drain.
18. No sewage or untreated effluent water would be discharged through storm water drains.
19. Onsite sewage treatment of capacity of treating 100% waste water to be installed. The installation of the Sewage Treatment Plant (STP) shall be certified by an independent expert and a report in this regard shall be submitted to the Ministry before the project is commissioned for operation. Treated waste water shall be reused on site for landscape, flushing, cooling tower, and other end-uses. Excess treated water shall be discharged as per statutory norms notified by Ministry of Environment, Forest and Climate Change. Natural treatment systems shall be promoted.
20. Periodical monitoring of water quality of treated sewage shall be conducted. Necessary measures should be made to mitigate the odor problem from STP.
21. Sludge from the onsite sewage treatment, including septic tanks, shall be collected, conveyed and disposed as per the Ministry of Urban Development, Centre Public Health and

Environmental Engineering Organization (CPHEEO) Manual on Sewerage and Sewage Treatment Systems, 2013.

4. Noise monitoring and prevention:
 1. Ambient noise levels shall conform to residential area/commercial area/industrial area/silence zone both during day and night as per Noise Pollution (Control and Regulation) Rules, 2000. Incremental pollution loads on the ambient air and noise quality shall be closely monitored during construction phase. Adequate measures shall be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB / SPCB.
 2. Noise level survey shall be carried as per the prescribed guidelines and report in this regard shall be submitted to Regional Officer of the Ministry as a part of six-monthly compliance report.
 3. Acoustic enclosures for DG sets, noise barriers for ground-run bays, ear plugs for operating personnel shall be implemented as mitigation measures for noise impact due to ground sources.
5. Energy Conservation measures:
 1. Compliance with the Energy Conservation Building Code (ECBC) of Bureau of Energy Efficiency shall be ensured. Buildings in the States which have notified their own ECBC, shall comply with the State ECBC.
 2. Outdoor and common area lighting shall be LED.
 3. Concept of passive solar design that minimize energy consumption in buildings by using design elements, such as building orientation, landscaping, efficient building envelope, appropriate fenestration, increased day lighting design and thermal mass etc. shall be incorporated in the building design. Wall, window, and roof u-values shall be as per ECBC specifications.
 4. Energy conservation measures like installation of CFLs/ LED for the lighting the area outside the building should be integral part of the project design and should be in place before project commissioning.
 5. Solar, wind or other Renewable Energy shall be installed to meet electricity generation equivalent to 1% of the demand load or as per the state level/ local building bye-laws requirement, whichever is higher.
 6. Solar power shall be used for lighting in the apartment to reduce the power load on grid. Separate electric meter shall be installed for solar power. Solar water heating shall be provided to meet 20% of the hot water demand of the commercial and institutional building or as per the requirement of the local building bye-laws, whichever is higher. Residential buildings are also recommended to meet its hot water demand from solar water heaters, as far as possible.
6. Waste Management :
 1. A certificate from the competent authority handling municipal solid wastes, indicating the existing civic capacities of handling and their adequacy to cater to the M.S.W. generated from project shall be obtained.
 2. Disposal of muck during construction phase shall not create any adverse effect on the neighboring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.
 3. Separate wet and dry bins must be provided in each unit and at the ground level for facilitating segregation of waste. Solid waste shall be segregated into wet garbage and inert materials.
 4. Organic waste compost/ Vermiculture pit/ Organic Waste Converter within the premises with a minimum capacity of 0.3 kg /person/day must be installed.
 5. All non-biodegradable waste shall be handed over to authorized recyclers for which a written tie up must be done with the authorized recyclers.
 6. Any hazardous waste generated during construction phase, shall be disposed off as per applicable rules and norms with necessary approvals of the State Pollution Control Board.
 7. Use of environment friendly materials in bricks, blocks and other construction materials, shall be required for at least 20% of the construction material quantity. These include Fly Ash

- bricks, hollow bricks, AACs, Fly Ash Lime Gypsum blocks, Compressed earth blocks, and other environment friendly materials.
8. Fly ash should be used as building material in the construction as per the provision of Fly Ash Notification of September, 1999 and amended as on 27th August, 2003 and 25th January, 2016. Ready mixed concrete must be used in building construction.
 9. Any wastes from construction and demolition activities related thereto shall be managed so as to strictly conform to the Construction and Demolition Rules, 2016.
 10. Used CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/ rules of the regulatory authority to avoid mercury contamination.
7. Green Cover:
1. No tree can be felled/transplant unless exigencies demand. Where absolutely necessary, tree felling shall be with prior permission from the concerned regulatory authority. Old trees should be retained based on girth and age regulations as may be prescribed by the Forest Department. Plantations to be ensured species (cut) to species (planted).
 2. A minimum of 1 tree for every 80 sqm of land should be planted and maintained. The existing trees will be counted for this purpose. The landscape planning should include plantation of native species. The species with heavy foliage, broad leaves and wide canopy cover are desirable. Water intensive and/or invasive species should not be used for landscaping.
 3. Where the trees need to be cut with prior permission from the concerned local Authority, compensatory plantation in the ratio of 1:10 (i.e. planting of 10 trees for every 1 tree that is cut) shall be done and maintained. Plantations to be ensured species (cut) to species (planted). Area for green belt development shall be provided as per the details provided in the project document.
 4. Topsoil should be stripped to a depth of 20 cm from the areas proposed for buildings, roads, paved areas, and external services. It should be stockpiled appropriately in designated areas and reapplied during plantation of the proposed vegetation on site.
8. Transport:
1. A comprehensive mobility plan, as per MoUD best practices guidelines (URDPFI), shall be prepared to include motorized, non-motorized, public, and private networks. Road should be designed with due consideration for environment, and safety of users. The road system can be designed with these basic criteria.
 - a. Hierarchy of roads with proper segregation of vehicular and pedestrian traffic.
 - b. Traffic calming measures.
 - c. Proper design of entry and exit points.
 - d. Parking norms as per local regulation.
 2. Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards be operated only during non-peak hours.
 3. A detailed traffic management and traffic decongestion plan shall be drawn up to ensure that the current level of service of the roads within a 05 kms radius of the project is maintained and improved upon after the implementation of the project. This plan should be based on cumulative impact of all development and increased habitation being carried out or proposed to be carried out by the project or other agencies in this 05 Kms radius of the site in different scenarios of space and time and the traffic management plan shall be duly validated and certified by the State Urban Development department and the P.W.D./ competent authority for road augmentation and shall also have their consent to the implementation of components of the plan which involve the participation of these departments.
9. Human health issues :
1. All workers working at the construction site and involved in loading, unloading, carriage of construction material and construction debris or working in any area with dust pollution shall be provided with dust mask.
 2. For indoor air quality the ventilation provisions as per National Building Code of India.
 3. Emergency preparedness plan based on the Hazard identification and Risk Assessment (HIRA) and Disaster Management Plan shall be implemented.
 4. Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP,

- safe drinking water, medical health care, crèche etc. The housing may be in the form of temporary structures to be removed after the completion of the project.
5. Occupational health surveillance of the workers shall be done on a regular basis.
 6. A First Aid Room shall be provided in the project both during construction and operations of the project.
10. Corporate Environment Responsibility:
1. The project proponent shall comply with the provisions contained in this Ministry's OM vide F.No. 22-65/2017-IA.III dated 1st May 2018, as applicable, regarding Corporate Environment Responsibility.
 2. The company shall have a well laid down environmental policy duly approved by the Board of Directors. The environmental policy should prescribe for standard operating procedures to have proper checks and balances and to bring into focus any infringements/deviation/violation of the environmental / forest / wildlife norms / conditions. The company shall have defined system of reporting infringements / deviation / violation of the environmental / forest / wildlife norms / conditions and / or shareholders / stake holders. The copy of the board resolution in this regard shall be submitted to the MoEF&CC as a part of six-monthly report.
 3. A separate Environmental Cell both at the project and company head quarter level, with qualified personnel shall be set up under the control of senior Executive, who will directly to the head of the organization.
 4. Action plan for implementing EMP and environmental conditions along with responsibility matrix of the company shall be prepared and shall be duly approved by competent authority. The year wise funds earmarked for environmental protection measures shall be kept in separate account and not to be diverted for any other purpose. Year wise progress of implementation of action plan shall be reported to the Ministry/Regional Office along with the Six Monthly Compliance Report.
11. Miscellaneous:
1. The project proponent shall prominently advertise it at least in two local newspapers of the District or State, of which one shall be in the vernacular language within seven days indicating that the project has been accorded environment clearance and the details of MoEFCC/SEIAA website where it is displayed.
 2. The copies of the environmental clearance shall be submitted by the project proponents to the Heads of local bodies, Panchayats and Municipal Bodies in addition to the relevant offices of the Government who in turn has to display the same for 30 days from the date of receipt.
 3. The project proponent shall upload the status of compliance of the stipulated environment clearance conditions, including results of monitored data on their website and update the same on half-yearly basis.
 4. The project proponent shall submit six-monthly reports on the status of the compliance of the stipulated environmental conditions on the website of the ministry of Environment, Forest and Climate Change at environment clearance portal.
 5. The project proponent shall submit the environmental statement for each financial year in Form-V to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently and put on the website of the company.
 6. The project proponent shall inform the Regional Office as well as the Ministry, the date of financial closure and final approval of the project by the concerned authorities, commencing the land development work and start of production operation by the project.
 7. The project authorities must strictly adhere to the stipulations made by the State Pollution Control Board and the State Government.
 8. The project proponent shall abide by all the commitments and recommendations made in the EIA/EMP report, commitment made during Public Hearing and also that during their presentation to the Expert Appraisal Committee.
 9. No further expansion or modifications in the plant shall be carried out without prior approval of the Ministry of Environment, Forests and Climate Change (MoEF&CC).
 10. Concealing factual data or submission of false/fabricated data may result in revocation of this environmental clearance and attract action under the provisions of Environment (Protection) Act, 1986.

Minutes of 738th SEAC-1 Meeting Dated 27/03/2023

11. The Ministry may revoke or suspend the clearance, if implementation of any of the above conditions is not satisfactory.
12. The Ministry reserves the right to stipulate additional conditions if found necessary. The Company in a time bound manner shall implement these conditions.
13. The Regional Office of this Ministry shall monitor compliance of the stipulated conditions. The project authorities should extend full cooperation to the officer (s) of the Regional Office by furnishing the requisite data / information/monitoring reports.
14. The above conditions shall be enforced, inter-alia under the provisions of the Water (Prevention & Control of Pollution) Act, 1974, the Air (Prevention & Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986, Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016 and the Public Liability Insurance Act, 1991 along with their amendments and Rules and any other orders passed by the Hon'ble Supreme Court of India / High Courts and any other Court of Law relating to the subject matter.
15. Any appeal against this EC shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.