PHASEWISE PROJECT COMPONENTS FOR RERA REGISTRATION PURPOSE



AREA DIAGRAM (PHASE 02)

PHASE 02					
AREA STATEMENT					
TITLE	NO.	SHAPE	LENGTH (L) (IN MM)	WIDTH (W) (IN MM)	AREA (L X W) (IN SQM)
ADDITION					
S1	1	REC	33401	25727	859.315
S2	1	REC	58520	18175	1063.601
S3	1	AS PER POLYLINE			152.664
TOTAL PHASE 02 (A1)					2075.580
PHASE 02 AREA=					0.5 ACRES

PHASE-1

1. TOWER-A
2. TOWER-B1
3. TOWER-B2
4. TOWER-C1
5. COMMUNITY 01
6. COMMUNITY 02
7. COMMUNITY 03
8. COMMUNITY 04
9. COMMERCIAL 01
10. COMMERCIAL 02
11. COMMERCIAL 03
12. COMMERCIAL 04
13. BASEMENT
14. STP
15. UGT
16. ESS
17. GUARD ROOM
18. HR METER ROOM
19. SWIMMING POOL

PHASE-2

FUTURE EXPANSION & COMMUNITY

PHASE-02 AREA : 0.5 ACRES

TOTAL AREA=	10.4625 ACRES	42340.168 Sq.Mt.
PHASE 01 AREA=	9.950 ACRES	40264.588 Sq.Mt.
PHASE 02 AREA=	0.513 ACRES	2075.580 Sq.Mt.



SITE PLAN

DENSITY						
		UNIT	No. of Towers	Total No. of Units	Population per Unit	Total Population
SITE LAYOUT	TOWER (A)	UNIT 3A	1	132	5	660
		UNIT 3B (DUPLEX) (3BL+3BU)		4	5	20
	TOWER B1	UNIT 6A	1	66	5	330
		UNIT 6B (DUPLEX) (4BL+4BU)		2	5	10
	TOWER B2	UNIT 4A	1	66	5	330
		UNIT 4B (DUPLEX) (4BL+4BU)		2	5	10
	TOWER C1	UNIT 5A	1	1	5	5
		UNIT 5A		32	5	160
		UNIT 5B		34	5	170
		UNIT 5C (DUPLEX) (5CL+5CU)		2	5	10
	TOTAL	TOTAL MAIN UNITS		341		1,705
	TOWER C1	SERVICE PERSONNEL		69	2	138
	TOTAL	TOTAL (SERVICE PERSONNEL)		69		138
	G. TOTAL	G. TOTAL	4			1,843

RERA CARPET			
		UNIT	RERA CARPET
SITE LAYOUT	TOWER (A)	UNIT 3A	149.550
		UNIT 3B (DUPLEX) (3BL+3BU)	220.506
	TOWER B1 & B2	UNIT 6A	205.433
		UNIT 6B (DUPLEX) (4BL+4BU)	309.385
	TOWER C1	UNIT 5A	261.091
		UNIT 5A	261.091
		UNIT 5B	261.091
		UNIT 5C (DUPLEX) (5CL+5CU)	386.836
	TOWER C1	SERVICE PERSONNEL	13.000

FLOOR WISE FAR AREA STATEMENT

FLOORS	TOWER-A			TOWER-B1 & B2			TOWER-C1			COMMUNITY 01			COMMUNITY 02			COMMUNITY 03			COMMUNITY 04			TOTAL FOR RESIDENTIAL	COMMERCIAL 01			COMMERCIAL 02			COMMERCIAL 03 (BASEMENT) (BELOW COMMUNITY 03)			COMMERCIAL 04 (BASEMENT) (BELOW COMMUNITY 02)			TOTAL FOR COMMERCIAL
	(G+ 35)			(G+ 35)			(G+ 36)			(G+1)			(G)			(G+1)			(G+1)				(G+ 3)			(G) (BELOW C1 TOWER)								
	FAR	NON FAR	BUILT UP AREA	FAR	NON FAR	BUILT UP AREA	FAR	NON FAR	BUILT UP AREA	FAR	NON FAR	BUILT UP AREA	FAR	NON FAR	BUILT UP AREA	FAR	NON FAR	BUILT UP AREA	FAR	NON FAR	BUILT UP AREA		FAR	NON FAR	BUILT UP AREA	FAR	NON FAR	BUILT UP AREA	FAR	NON FAR	BUILT UP AREA	FAR	NON FAR	BUILT UP AREA	
GROUND COVERAGE AREA(BASEMENT FLOOR	1343.060			858.351			1835.601			480.000			272.660			480.000			348.458				350.804			168.563			0.000			0.000			
GROUND/ 1ST FLOOR	333.342	794.526	1127.873	276.709	502.260	778.969	388.844	1114.756	1494.599	480.000		463.835	178.635	82.660	261.296	480.000		476.198	401.296	38.850	419.955		350.804		344.754	333.195		359.195	240.825	57.475	298.300	231.840	58.400	290.240	1,143,711.031 SQ.MT.
1ST FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	535.348		77.838	412.976	399.502	57.475	457.395			411.566	58.400	469.966	293.545	11.245	234.789		284.390	69.019	333.408									
2ND FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269														284.390	69.019	333.408									
3 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.267														284.390	69.019	333.408									
4 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
5 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.267																									
6 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
7 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
8 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
9 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
10 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
11 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
12 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
13 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
14 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
15 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.267																									
16 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
17 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
18 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
19 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
20 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
21 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
22 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
23 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
24 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
25 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
26 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
27 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
28 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
29 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.267																									
30 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
31 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
32 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
33 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	639.626	144.641	764.269																									
34 FLOOR	753.322	358.587	911.909	501.408	122.059	623.447	620.442	143.825	764.267																									
35 FLOOR	783.728	345.343	893.023	501.408	122.059	623.447	639.626	144.641	764.269																									
36 FLOOR	446.286	59.812	506.098	286.500	71.247	357.747	620.442	143.825	764.267																									
							333.135		127.470	458.606																									
MUMTY + OHT BUA			206.279			128.556			111.944																95.0518									
TOTAL FAR OF SINGLE TOWER (STILT + TYPICAL FLOORS)	26,380.779		17,683.090			22,117.334			879.920				178.635			891.566			694.836				1,203.073			359.195			240.825			231.840			
NOS. OF TOWER	1		2			1			1				1			1			1				1			1			1			1			
NET TOTAL FAR	26,380.779		35,222.160			22,117.334			879.920				178.635			891.566			694.836			86,355.230	SQ.MT.		1,203.073			359.195			240.825			231.840			2,035.833 SQ.MT.
NET TOTAL GR. COVERAGE	1343.060		1717.829			1835.601			480.000			272.660			480.000			348.458			6,477.007	SQ.MT.		350.804			168.563			0.000			519.367	SQ.MT.
BUILT UP AREA PER TOWER		32816.111			22463.436			28453.248			927.230			261.296			946.164			734.743														
NET TOTAL BUILT UP AREA EXCLUDING BASEMENT		32816.111			44926.873			28453.248			927.230			261.296			946.164			734.743		1,09,065.664	SQ.MT.		1440.032			359.195			298.300			290.240			2,387.766 SQ.MT.
BUILT UP AREA AT BASEMENT (OTHER THAN COMMUNITY)																							39,229.031	SQ.MT.											
GUARD ROOM & HT METER ROOM																							28.000	SQ.MT.											
TOTAL BUILT UP AREA INCLUDING BASEMENT																							1,43,323.265	SQ.MT.											
TOTAL NON FAR AREA																							54,908.035	SQ.MT.											
GRAND TOTAL: BUILT UP AREA (INCLUDING RESIDENTIAL AND COMMERCIAL)																																		1,43,711.031	SQ.MT.

*ALL AREAS IN SQ.MT.

OVERALL SITE AREA STATEMENT						
A.	PLOT AREA			42,340.168	SQ.MT.	10.4625 ACRES
B.	COMMUNITY PLOT AREA SURRENDER TO GOVT.			4,243.912	SQ.MT.	1.0487 ACRES
C. (A-B)	SITE AREA AFTER LAND SURRENDER			38,096.237	SQ.MT.	9.414 ACRES
D.(4% of (A))	PERMISSIBLE COMMERCIAL PLOT AREA (4% OF PLOT AREA) (INCLUDING SURRENDERED COMMUNITY PLOT AREA)	4.0%		1,693.607	SQ.MT.	0.419 ACRES
E.(2.6% of (A))	PROPOSED COMMERCIAL PLOT AREA	2.6%		1,100.844	SQ.MT.	
F. (FAR on (E))	PERMISSIBLE F.A.R. FOR COMMERCIAL (1.75 (Main FAR))	*1.75*		*1,926.478*	*SQ.MT.*	
G. (FAR on (E))	PERMISSIBLE F.A.R. FOR COMMERCIAL (0.12 (Green Building (IGBC GOLD, Registration No-GH2300315, December 2023))	*0.12*		*132.101*	*SQ.MT.*	
H=F+G	TOTALPERMISSIBLE F.A.R. FOR COMMERCIAL (1.75 (Main FAR) + 0.12 (Green Building (IGBC GOLD, Registration No-GH2300315, December 2023)))	**1.87**		**2,058.579**	**SQ.MT.**	
I.	PROPOSED F.A.R. FOR COMMERCIAL 01			1,203.973	SQ.MT.	
J.	PROPOSED F.A.R. FOR COMMERCIAL 02 at Ground Level			359.195	SQ.MT.	
K.	PROPOSED F.A.R. FOR COMMERCIAL 03 in Basement (Below Community 01)			240.825	SQ.MT.	
L.	PROPOSED F.A.R. FOR COMMERCIAL 04 in Basement (Below Community 03)			231.840	SQ.MT.	
M.=I+J+K+L	TOTAL PROPOSED F.A.R. FOR COMMERCIAL	*1.849*		**2,035.833**	**SQ.MT.**	
	RETAIL SHOPPING FOR LOCAL NEEDS					
	MINIMUM REQUIRED FAR FOR RETAIL SHOPPING FOR LOCAL NEEDS @50% OF PROPOSED FAR	*50.00%*		**1,017.92**	**SQ.MT.**	
	PROPOSED FAR FOR RETAIL SHOPPING FOR LOCAL NEEDS (COMMERCIAL 02+ COMMERCIAL 03+COMMERCIAL 04)			831.859	SQ.MT.	
	PROPOSED FAR FOR RETAIL SHOPPING FOR LOCAL NEEDS (COMMERCIAL 01 (SECOND FLOOR))			284.390	SQ.MT.	
	TOTAL PROPOSED FAR FOR RETAIL SHOPPING FOR LOCAL NEEDS			**1,116.249**	**SQ.MT.**	
N.(on (E))	PERMISSIBLE GROUND COVERAGE FOR COMMERCIAL (@50% OF COMMERCIAL SITE AREA)	50.00%		550.422	SQ.MT.	
N1	PROPOSED GROUND COVERAGE OF COMMERCIAL 01			350.804	SQ.MT.	
N2	PROPOSED GROUND COVERAGE OF COMMERCIAL 02 at Ground Level			168.563	SQ.MT.	
O.	TOTAL PROPOSED GROUND COVERAGE FOR COMMERCIAL	47.18%		519.367	SQ.MT.	
P.=A-E	RESIDENTIAL PLOT AREA FOR FAR CALCULATION (INCLUDING SURRENDERED COMMUNITY PLOT AREA)	97.40%		41,239.324	SQ.MT.	10.190 ACRES
Q.	PERMISSIBLE GROUND COVERAGE FOR RESIDENTIAL(@35% OF SITE AREA)	0.35		14,433.763	SQ.MT.	
R.	PROPOSED GROUND COVERAGE FOR RESIDENTIAL	15.78%		6,505.607	SQ.MT.	
S.	PERMISSIBLE RESIDENTIAL F.A.R. (1.25(Main FAR)) (On P)	*1.25*		*51,549.153*	*SQ.MT.*	
T.	PERMISSIBLE RESIDENTIAL F.A.R. (TDR FAR)			*35,197.928*	*SQ.MT.*	
U.	PERMISSIBLE RESIDENTIAL F.A.R. (0.12 (Green Building (IGBC GOLD, Registration No-GH2300315, December 2023)) (On P)	*0.12*		*4,948.719*	*SQ.MT.*	
V.=S+T+U	PERMISSIBLE RESIDENTIAL F.A.R. (1.25(Main FAR) +TDR FAR+ 0.12 (Green Building (IGBC GOLD, Registration No-GH2300315, December 2023)) (On P)			**91,695.80**	**SQ.MT.**	
W.	PROPOSED RESIDENTIAL F.A.R			**86,355.230**	**SQ.MT.**	
X.	REQUIRED GREEN AREA (15 % PLOT AREA) (on plot area A)	0.15		6,353.025	SQ.MT.	
Y.	PROPOSED GREEN AREA	22.00%		9,316.927	SQ.MT.	

In lieu of 10% land to be surrendered in favour of Government for Affordable Group Housing, the colonizer/ developer deposits an amount at the rate three times the applicable collector rate, with following Transaction Nos.

Transaction No: TOWNIAC3000084303

Transaction No: TOWNIAC3000084248

DENSITY				
A1.	PERMISSIBLE POPULATION DENSITY (400 (ZONING)+ 125	525	PPA	
A2.	PERMISSIBLE NO OF PEOPLE	5,493	NOS	
A3.	TOTAL NUMBER OF PROPOSED MAIN UNITS	**341**	**NOS**	
A4.	TOTAL NUMBER OF PROPOSED SERVICE PERSONNEL	69	NOS	
A5.	PROPOSED TOTAL POLPULATION	1,843	Person	
A6.	PROPOSED TOTAL POLPULATION DENSITY	**176**	**PPA**	

PARKING						
B1.	REQUIRED CAR PARKING RESIDENTIAL (@1.5 ECS PER MAIN UNIT)	Nos Of Unit x 1.5	341	1.5	512	ECS
B2.	PROPOSED BASEMENT PARKING AREA				28591.089	SQ.MT.
B3.	PROPOSED ECS AS PER BASEMENT PARKING AREA @32				893	ECS
B4.	PROPOSED CAR PARKING BAYS (BASEMENT)				**800**	**NOS**
B5.	PROPOSED SURFACE PARKING AREA RESIDENTIAL				4,081.940	SQ.MT.
B6.	PROPOSED ECS AS PER SURFACE AREA @23 SQ.MT.				177	ECS
B7.	PROPOSED CAR PARKING (PHY. HANDICAPPED)				**2**	**NOS**
B8.	PROPOSED CAR PARKING BAYS (SURFACE)				**145**	**NOS**
B9.	PROPOSED CAR PARKING FOR RESIDENTIAL (BASEMENT+				947	NOS
B10.	REQUIRED CAR PARKING COMMERCIAL(1 ECS PER 50	2,035.833	-	50	41	ECS
B11.	PROPOSED SURFACE PARKING AREA COMMERCIAL				1,314.841	SQ.MT.
B12.	PPROPOSED ECS AS PER SURFACE AREA @23 SQ.MT.				57	ECS
B13.	PROPOSED CAR PARKING BAYS COMMERCIAL				**41**	**NOS**

FIRE TENDER PATH IS DESIGNED FOR 45 TON LOAD



SUBMISSION DRAWING

GENERAL NOTES:

1–ALL DIMENSIONS ARE IN MM UNLESS MENTIONED OTHERWISE (U.N.O.)
2–NO DIMENSIONS ARE TO BE SCALED FROM THIS DRAWING.

Checked and found ok for Public Hea: (Internal) Service only subject to comm: In forwarding letter No. 1331117 Dt/ 17/11/2024

DRAWING TITLE:

SITE PLAN

Superintending Engineer (HQ) Public Health Circle, Panchkula

PROJECT TITLE :

PROPOSED RESIDENTIAL COLONY UNDER NILP POLICY FOR THE AREA MEASURING 10.4625 ACRES (LICENCE NO 215 OF 2023 DATED 23/10/2023 (MIGRATION FROM LICENCE NO. 60 OF 2022 DATED 13.05.2022) IN SECTOR-63-A, GURUGRAM MANESAR URBAN COMPLEX BEING DEVELOPED BY PYRAMID & LID REALTORS LLP (EARLIER KNOWN AS SCJS BUILDWELL LLP)

CLIENT / OWNER :

SILVERGLADES HOMES LLP
506,5th FLOOR, TIME SQUARE BUILDING, B-BLOCK, SUSHANT LOK, PHASE-1, GURUGRAM - 122002, HARYANA, INDIA

JOB NO.

SCALE :

DATE :

NORTH.

DRAWING NO.

SG/DFI/SUB/AR/ SP/001

ARCHITECT'S SIGNATURE:

ANAND SHARMA

Digitally signed by ANAND SHARMA
Date: 2024.06.03 17:03:13 +05'30'

ANAND SHARMA (CA/95/18738)

OWNER'S SIGNATURE:

For Silverglades Homes LLP

Authorised Signatory

ARCHITECTS:-

DESIGN FORUM INTERNATIONAL

Address : K-47 , KAILASH COLONY , NEW DELHI -48
Phone : 011-46556600,46556601 , FAX - 46556601
Website: www.designforuminternational.com

DDT (N) MEMBER BPAC

S.T.P (HQ) Member BPAC

DTP (HQ) ATP (HQ)

SANCTIONED TO BE READ WITH THE OFFICE MEMO. 2925/5 DATED : 05/04/2024

(Dinesh Kumar) PA(HQ)